

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20709-00-00  
Spot: SENENW Sec/Twnshp/Rge: 3-9S-27W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: MOSIER A Well #: 5  
County: SHERIDAN Total Vertical Depth: 4030 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3700		
SURF	8.625	260	0	190 SX <b>130.98</b>
T1	2.875	3985		
PROD	5.5	4032	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/22/2009 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 480 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/22/2009 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 260' w/190 sxs cement.  
5 1/2" production casing set at 4032' w/175 sxs cement.  
TD 4030'. CIBP set at 3700'.  
Perforated 5 1/2" production casing at 2230' and 1440'.  
Ran tubing to 3030' - tagged bridge.  
Pulled tubing to 2936' - pumped 92 sxs cement with 200# hulls.  
Pulled tubing to 1908' - pumped 92 sxs cement with 200# hulls.  
Pulled tubing 904' - pumped 80 sxs cement with 100# hulls - cement to surface - pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 20 sxs cement.  
Connected to 8 5/8" surface casing - pumped 30 sxs cement.  
Max. P.S.I. 100#. S.I.P. 50#.  
Note: Operator requested 100% cement plug.

Perfs:

Top	Bot	Thru	Comments
3811	3979		LKC
3768	3772		TORONTO

INVOICED  
DATE 7-20-09  
INV. NO. 2010060041

RECEIVED  
JUN 01 2009  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING-TICKET 33159.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

*Handwritten initials*


## REPLACEMENT CARD

SKYLINE PETROLEUM  
 P. O. BOX 70 #5 "A" MOSIER 3-9-27W  
 HAYS, KS 67601 SE NE NW

CONTR BIG SPRINGS DRILLING, INC. CITY SHERIDAN

GEOL \_\_\_\_\_ FIELD MCFADDEN NORTH

ELV 2646 KB SPD 10/25/83 CARD ISSUED 12/15/83 # P 100 BO & 100 BWPD  
2641 GL LKC 3899-3979 OA



SMP	Top	Depth/Datum
TOP	.....	3536-890
HEEB	.....	3744-1098
TOR	.....	3768-1122
LKC	.....	3782-1136
BKC	.....	4010-1364
RTD	.....	4030-1384
LTD	.....	4032-1386

API 15-179-20,709  
 8 5/8 " 260 / 190SX; 5 1/2 " 4032 / 175SX  
 DST (1) 3740-3814 (TOR, LKC) / 60-45-30-45, REC 40' OCM  
 310' OCWM, SIP 789-868#, FP 74-148, 180-190#  
 DST (2) 3814-3838 (LKC) / 60-45-0-0, REC 2205' OCWM, 124  
 OIL SPTD MDY WTR, 248' MDY WTR, ISIP 889#, IFP 84-296#  
 DST (3) 3850-3865 (LKC) 60-45-30-45, REC 5' FREE OIL, 25  
 OCMW, 1220' SW, SIP 1080-1080#, FP 52-413, 440-550#  
 DST (4) 3896-3942 (LKC) 60-45-30-45, REC 680' FREE OIL,  
 240' MCO, 120' HOCM, 60' OCWM, 120' MDY WTR, SIP 868-  
 868#, FP 84-370, 423-460#  
 MICT - CO, PF (LKC K) 1:3978 & (LKC J) 1:3959, SWB DWN  
 SSO, NAT, AC 1000G (15% NE), SWB DWN, REC 4.3 BF (3.5%  
 OIL) / 30", 4.5 BF (42% OIL) / NX 30", 4.1 BF (44% OIL) / NX  
 30", 4.2 BF (45% OIL) / NX 30", RE-AC 2000G (28% NE), SION.  
 (over)

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

INFO RELEASED: 5/31/84 - WAS TIGHT HOLE

## REPLACEMENT CARD

SKYLINE PETROLEUM # 5 "A" MOSIER 3-9-27W  
 SE NE NW

FL LEVEL 800' FROM SURFACE, SWB DWN, 600' OFF BTM, REC 8.4 BF (45% OIL) / 15", 8.8 BF (43% OIL) /  
 15", 8.3 BF (47% OIL) / 15", SET RBP AT 3940', SWB DWN DRY, PF (LKC H) 1:3911 & (LKC G) 1/2900, SWB  
 DWN, REC 5 BFPH (95% OIL) / 2 HRS, NAT, AC 1000G (15% NE), SWB DWN 300' OFF BTM, REC 7.6 BF (75%  
 OIL) / 15", 8.1 BF (77% OIL) / 15", SION, 1800' FIH (900' OIL, 900' WTR), PULLED PLUG, RE-PF (LKC) 3977-  
 79, 3958-60, 3911-13, & 3899-3901, W:2 SPF, T & R, POP, P 100 BO & 100 BWP, (GR 40%), 11/18/83