

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00274-00-00
Spot: SE Sec/Twnshp/Rge: 10-22S-33W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BECKER Well #: 1
County: FINNEY Total Vertical Depth: 2682 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	313		WITH 250 SX CMT
PROD 7		2681	0	WITH 750 SX CMT 87.17

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/06/2009 6:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (785) 623-1066

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT. PLUG AT 1200' WITH GEL WATER & 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 05/07/2009 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 50 SX CMT AT 2510'. TAG BOTTOM PLUG AFTER 12 HOURS. LOAD HOLE WITH GEL WATER. 1ST PLUG AT 1200' WITH 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60-0' WITH 20 SX CMT. PUMPED 13 SX CMT DOWN 7" X 10 3/4" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2620	2625		KRIDER
2605	2610		HERRINGTON

INVOICED

DATE 7-20-09

INV. NO. 2010060042

RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

MAY 15 2009

KCC DODGE CITY