

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20554-00-00
Spot: SESE Sec/Twnshp/Rge: 36-28S-16W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: V MACHESNEY Well #: A-1
County: KIOWA Total Vertical Depth: 4850 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	445		WITH 400 SX CMT
PROD	4.5	4813	2420	WITH 220 SX CMT

157.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2009 2:40 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4625' & 4 SX CMT. PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2009 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4600' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 475' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4696	4710		MISSISSIPPI
4672	4676		CHEROKEE

INVOICED
DATE 7-20-09
INV. NO. 2010060042

RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
MAY 28 2009
KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

[Handwritten initials]