

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01909-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 31-17S-10W  
2296 feet from S Section Line, 4274 feet from E Section Line  
Lease Name: PATZNER Well #: 2-B  
County: ELLSWORTH Total Vertical Depth: 3274 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W 47TH ST STE 412  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	12.5	565		UNKNOWN
COND	15.5	100		UNKNOWN <b>106.41</b>
PROD	7	3269		UNKNOWN

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2009 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/14/2009 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU RUN TUBING DOWN TO 2400', ENCOUNTERED SOLID BRIDGE. PUMP 20 SX'S GEL FOLLOWED BY 50 SX'S CEMENT WITH 100#"S COTTON HULLS. PERFORATE @ 1250', 950', AND 615'. PULL TUBING TO 1250' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 950' AND PUMP 50 SX'S CEMENT WITH 1 SACK CALCIUM CHROLIDE. PULL TUBING UP TO LET PLUG SET UP. RE-TAG TOP PLUG AT 1000'. RUN TUBING BACK DOWN TO 950' AND PUMP 35 MORE SACKS CEMENT. PULL TUBING TO 615' AND USED 200 SX'S CEMENT TO CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3269	3274		OPEN HOLE

**INVOICED**  
DATE 7-20-09  
INV. NO. 2010060043

RECEIVED  
JUN 01 2009  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #5744. COPELAND TICKET #C-35335.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)