

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20840-00-00
Spot: NWSW Sec/Twnshp/Rge: 35-29S-40W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: DWIGHT LEROY Well #: 1-35
County: STANTON Total Vertical Depth: 5750 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5550		WITH 2 SX CMT
SURF	8.625	1706		WITH 650 SX CMT
DVT		2905		WITH 600 SX CMT
PROD	4.5	5750	0	WITH 850 SX CMT

186.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2008 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TONY ATON Company: PRESCO WESTERN Phone: (620) 655-1958

Proposed Plugging Method: CIBP @ 5560' & 2 SX CMT. PLUG AT 1740' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 60-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2009 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5550' WITH 2 SX CMT. 10/3/08: PUMP 4 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO FILL. PUMP 50 SX CMT AT 1740'. CEASE OPERATIONS UNTIL PARTNER APPROVAL TO PLUG & ABANDON RECEIVED. 5/19/09: RAN TBG TO 690'. PUMP 50 SX CMT AT 690-0'. TOOH W/TBG. TOP OUT WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5612	5620		

INVOICED
DATE 7-20-09
INV. NO. 2010060044

RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
MAY 28 2009
KCC DODGE CITY

Signed: [Signature]
(TECHNICIAN)