

15-163-02583-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 16 Twp. 10S Rge. 18 (X) W (W)

Location as "NE/CNW/SW" or footage from lines C N/2 SW/4

Lease Owner Davis Bros.

Lease Name Ordway "C" Well No. 4

Office Address 14 East Third Street, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed September 25, 19 58

Application for plugging filed September 25, 19 58

Application for plugging approved September 25, 19 58

Plugging commenced September 25, 19 58

Plugging completed September 25, 19 58

Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	165'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 500'; set plug, cemented with 20 sacks of cement.

Filled hole with heavy drilling mud to 150'; set plug, cemented with 15 sacks of cement.

Filled hole with heavy drilling mud to 40'; set plug, cemented with 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1958

My commission expires May 17, 1962.

Mildred Seom Notary Public.

PLUGGING  
FILE SEC 16T 10 R 18W  
BOOK PAGE 134 LINE 33

10-23-58

DRILLER'S WELL LOG

Davis Bros.-Ordway "C" # 4 located in  
C N/2 SW/4 Sec. 16-10S-18W,  
Rooks County, Kansas

Commenced: September 13, 1958  
Completed: September 25, 1958  
Elevation: 2118 KB

Casing 8 5/8" @ 165'  
Cemented w/130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface clay	0	40
Shale	40	80
Sand	80	120
Shale	120	630
Sand and shale	630	840
Shale and shells	840	980
Sand	980	1160
Shale and shells	1160	1220
Shale	1220	1480
Anhydrite	1480	1516
Shale	1516	1970
Shale w/lime	1970	2435
Lime and shale streaks	2435	2674
Shale and lime	2674	2774
Lime and shale	2774	2900
Shale and lime	2900	3107
Lime	3107	3171
Lime and shale	3171	3241
Lime	3241	3281
Lime and shale	3281	3349
Lime	3349	3497
Shale	3497	3500
Lime	3500	3584
Shale	3584	3625
Lime w/shale	3625	3675
Conglomerate and chert	3675	3776
Chert and simpson dolo.	3776	3799
Lime	3799	3909 TD

Summary of Formation

Anhydrite	1500'
Topeka	3102'
Heebner	3319'
Toronto	3347'
Lansing	3364'
Base K.C.	3605'
Conglomerate	3655'
Simpson Shale	3777'
Simpson Dolo.	3785'
Arbuckle Dolo.	3882'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me  
this 22nd. day of October, 1958.

TRANSIT CORPORATION

By Paul E. Gathers

My Commission expires May 17, 1962.

Mildred Jean  
Notary Public

PLUGGING  
FILE SEC 16 T 10R 18W  
BOOK PAGE 134 LINE 33

RECEIVED  
OCT 28 1958  
TRANSIT CORPORATION