


15-163-00498-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 13 Twp. 10S Rge. 18W (E) (W)
Location as "NE/CNW&SW&" or footage from lines NW NW NE
Lease Owner Murfin Drilling Co.
Lease Name Schleuter Well No. 1
Office Address 507 Union Nat. Bank Bldg - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-4 19 53
Application for plugging filed 6-19 19 56
Application for plugging approved 6-19 19 56
Plugging commenced 6-29 19 56
Plugging completed 6-29 19 56
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production March 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Kansas City Depth to top 3386 Bottom _____ Total Depth of Well 3754 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	none
				5 1/2	3757	2574'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crush rock to 3530.
Dump 4 sax cement with dump bailer, top of cement 3505.
Filled hole with mud to 195, set rock bridge.
Dump 15 sx. cement. Top of Cement 160.
Filled with mud to 35', set rock bridge.
Dump 10 sx. cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 56.

Betty Spriggs Notary Public.

My commission expires 6-13-59.

7-18-56

PLUGGING
FILE SEC. 13 T. 10 R. 18W
BOOK PAGE 72 LINE 38

WELL LOG

15-163-00498-0000

COMPANY Murfin Drilling Company

SEC. 13 T. 10 R. 18W

FARM Schleuter NO. #1

LOC. NW NW NE

TOTAL DEPTH 3754

COMM. 8-26-53


COMP. 9-4-53

COUNTY Rooks County
KANSAS

BHDT OR TREATED

CONTRACTOR Murfin Drilling Company

ISSUED



CASING

20 10
15 8 5/8 200'
12 6
13 5 1/2" 3757'

ELEVATION 2164 R.B.

PRODUCTION 25 bbl. p/d

FIGURES INDICATE BOTTOM OF FORMATIONS

30 Shale
70 Sand-Shale
630 Shale-Shells
740 Sand-Iron
810 Red Bed-Shale
960 Sand-Iron
1190 Shale-Shells
1375 Sand (Hard)
1485 Shale-Shells
1522 Anhydrite
1825 Shale-Shells
1900 Salt-Shale
2280 Shale-Lime
2510 Lime-Shale
3110 Shale-Lime
3290 Lime-Shale
3665 Lime
3675 Cherty-Shale
3754 Lime - T.D.

TOPS

Anhydrite 1485
Topeka 3119
Heebner 3344
Toronto 3365
Lansing K. C. 3386
K. C. Lime 3625
Congl. 3651
Simpson 3724
Arbuckle 3748
R. T. D. 3754

DST #13468-3488 - open 45 min. 22' watery mud with few specks of oil. Shut in 15 min. BHP 1075# psi.

DST #2 3541-3555 - strong blow 1 hr. 85' oil, 120' mud cut oil. IFP 0, FFP 80#. Shut in 15 min. BHP 960#. psi.

PLUGGING
FILE SEC. 13 T. 10 R. 18W
BOOK PAGE 72 LINE 38

State of KANSAS }
County of SEDGWICK } ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Schleuter #1 well.

Subscribed and sworn to before me this 7th day of December 19 53

My Commission Expires: June 13, 1959.
7-20-57

W. R. Murfin

Betty Spriggs
NOTARY PUBLIC