

15-163-01114-0000

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 134-15  
LOCATION NE NE SE  
SEC. 15 TWP. 10 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Miller

Operator Republic <sup>Natural</sup> Natl Gas Co. Address Ellinwood, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3704 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

9 5/8" at 258' circulated with cement - 5 1/2" at 3740' with  
100 sax cement behind - Lane Wells plugs to 3584' - perforations  
at 3451' , Sand, chat and plugs to 3400', set 4 sax cement  
with dump bailer, pulled approx 2000' 5 1/2", mud to 258', set  
rock and 20 sax cement, mud to 30', set rock and 10 sax cement  
to bottom cellar.

**PLUGGING**  
FILE SEC 13 T 10 R 18W  
BOOK PAGE 134 LINE 15

RECEIVED  
11-16-53  
DISTRICT CONSERVATION  
WICHITA, KANSAS

*Edna Petty*  
District Conservation Agent  
Date 11-15-53