

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 72-38

LOCATION NW NW NE

SEC. 13 TWP. 10 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schleuter

Operator Murfin Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3752 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3752' with 125

sax cement behind. Lane Wells plugs to 3750', perforated at 3542'

Filled with chat to 3530', set 4 sax cement with dump bailer,

pulled 2700' 5 1/2" - heavy mud to 195', set rock and 15 sax

cement, mud to 35', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 6-30-56

7-2-56

PLUGGING
FILE SEC. 13 T. 10 R. 18W
BOOK PAGE 12 LI. E. 38