

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE NE NW

SEC. 16 TWP. 10 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease _____ Ordway _____

Operator Skelly Oil Co Address Hutchinson, Kans Box 691

Field _____ County Rooks

Total Depth 3775 Feet.

Plugging Contractor Wentworth Drg Co & Halliburton Co

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 279' circulated with cement.

Spotted 25 sax cement on bottom through drill pipe, mud to 3550'

set plug and spotted 50 sax cement through drill pipe at 3550,

heavy mud to 279', set cementing plug and 25 sax cement to 204'

heavy mud to 70', set cementing plug, 1/2 sack hulls and

25 sax cement to bottom cellar.

Cementing by Halliburton Co.

E. Lee
District Conservation Agent

Date 2-10-55

2-12-55

PLUGGING
FILE SEC 16 T 10 R 18
BOOK PAGE 96 LINE 15