

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

10-3-61

TO: Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks
Location: SW NW NE Sec. 16 Twp. 10 Rge. _____ (E) (W) 18
Name of Field: _____ Total Depth: 3535

I have this date completed supervision of plugging of:

lease Name: Ordway Well No. A-1

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 29 Month 9 Year 61

The above well was plugged as follows:

8 5/8" 182' circulated with cement - 5 1/2" 3535' with 125 sax cement -

PB to 3455' - perf 3444'

Filled with sand to 3430', set 4 sax cement with dump bailer - pulled 1570'

5 1/2" to 560' - circulated hole with heavy mud through 5 1/2" at 560' (18 sax Gel

displaced 20 sax cement through 5 1/2" at 560' - heavy mud to 250' - displaced

20 sax cement through 5 1/2" at 250' - heavy mud to 35', set bridge and

cemented to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

10/18/61
3858-W