

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

07-26-76

API Number 15 - - (of this well)

Operator's Full Name K & G Oil Co.

Complete Address Drawer 340, Plainville, Kansas 67663

Lease Name Ordway Well No. 4

Location SW SW NW Sec. 16 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3770'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address License No.

Operation Completed: Hour 11 A Day 21 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 3770' 8 5/8 csg set 855' cwc 450 sk.

5 1/2 csg set 3767' cw 200 sx cem.

5 1/2 csg sq. thru Dak. Sec. & circ to surface. No pipe recovered.

Allied Cementing Co. mixed & pumped down 5 1/2 csg with 100 sk comm 4% -displaced
with 30 sk gel & water W/300 lbs hulls -capped with 100 lbs hulls, plug & 50 sk
comm 4% & shutin. PP 700 lbs. SIP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3502-11