

ORIGINAL

CONFIDENTIAL

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

RECEIVED

SEP 06 2006 Form Must Be Typed

AMENDED

WELL COMPLETION FORM WELL HISTORY - DESCRIPTION OF WELL & LEASE CONSERVATION DIVISION WICHITA, KS

Operator: License # 33365 Name: Layne Energy Operating, LLC Address: 1900 Shawnee Mission Parkway City/State/Zip: Mission Woods, KS 66205 Purchaser: Operator Contact Person: M. B. Natrass Phone: (913) 748-3987 Contractor: Name: Thornton Air Rotary License: 33606

Wellsite Geologist: Designate Type of Completion: [X] New Well [ ] Re-Entry [ ] Workover [ ] Oil [ ] SWD [ ] SIOW [ ] Temp. Abd. [X] Gas [ ] ENHR [ ] SIGW [ ] Dry [ ] Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows: Operator: Well Name: Original Comp. Date: Original Total Depth: [ ] Deepening [ ] Re-perf. [ ] Conv. to Enhr./SWD [ ] Plug Back [ ] Plug Back Total Depth [ ] Commingled [ ] Dual Completion [ ] Other (SWD or Enhr.?)

1/6/2006 Spud Date or Recompletion Date 1/10/2006 Date Reached TD 7/17/2006 Completion Date or Recompletion Date

API No. 15 - 205-26275-06-06 County: Wilson SW NE NE NE Sec. 7 Twp. 30 S. R. 16 [X] East [ ] West 450 feet from S / (N) (circle one) Line of Section 450 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner: (circle one) NE SE NW SW Lease Name: Kammerer B&B Well #: 1-7 Field Name: Neodesha Producing Formation: Cherokee Coals Elevation: Ground: 797 Kelly Bushing: Total Depth: 913 Plug Back Total Depth: 903 Amount of Surface Pipe Set and Cemented at 44 Feet Multiple Stage Cementing Collar Used? [ ] Yes [X] No If yes, show depth set Feet If Alternate II completion, cement circulated from 910 feet depth to Surface w/ 100 sx cmt.

Drilling Fluid Management Plan Alt II N41020-08 (Data must be collected from the Reserve Pit) Chloride content N/A ppm Fluid volume bbls Dewatering method used N/A - Air Drilled Location of fluid disposal if hauled offsite: Operator Name: Lease Name: License No.: Quarter Sec. Twp. S. R. [ ] East [ ] West County: Docket No.:

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature] Title: Agent Date: 9/5/06 Subscribed and sworn to before me this 5 day of September 20 06. [Signature] Notary Public: [Signature] Date Commission Expires: 12/28/09

KCC Office Use ONLY [X] Letter of Confidentiality Attached If Denied, Yes [ ] Date: Wireline Log Received Geologist Report Received UIC Distribution

NOTARY PUBLIC - State Of Kansas BROOKE C. MAXFIELD My Appl. Exp. 12/28/09

Operator Name: Layne Energy Operating, LLC Lease Name: Kammerer B&B Well #: 1-7  
 Sec. 7 Twp. 30 S. R. 16  East  West County: Wilson

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run:  Compensated Density Neutron Dual Induction	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:70%;">Name</td> <td style="width:15%;">Top</td> <td style="width:15%;">Datum</td> </tr> <tr> <td>Pawnee Lime</td> <td>634 GL</td> <td>260</td> </tr> <tr> <td>Excello Shale</td> <td>736 GL</td> <td>135</td> </tr> <tr> <td>V Shale</td> <td>806 GL</td> <td>62</td> </tr> <tr> <td>Mineral Coal</td> <td>845 GL</td> <td>27</td> </tr> </table>	Name	Top	Datum	Pawnee Lime	634 GL	260	Excello Shale	736 GL	135	V Shale	806 GL	62	Mineral Coal	845 GL	27
Name	Top	Datum														
Pawnee Lime	634 GL	260														
Excello Shale	736 GL	135														
V Shale	806 GL	62														
Mineral Coal	845 GL	27														

KCC  
SEP 05 2006  
CONFIDENTIAL

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacjs Used	Type and Percent Additives
Surface	11	8.65	24	44'	Class A	60	Type 1 cement
Casing	6.75	4.5	10.5	910'	Thick Set	100	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>
	See Attached	<div style="border: 1px solid black; padding: 5px; width: fit-content; margin: auto;"> <b>RECEIVED</b>                      KANSAS CORPORATION COMMISSION                      SEP 06 2006                      CONSERVATION DIVISION                      WICHITA, KS                 </div>

TUBING RECORD		Size	Set At	Packer At	Liner Run		
		2 3/8"	870'		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Date of First, Resumerd Production, SWD or Enhr. 8/23/2006			Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
	0	6	28				

Disposition of Gas  Vented  Sold  Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled

Production Interval  Other (Specify) \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 06 2006

CONSERVATION DIVISION  
WICHITA, KS

**Operator Name:** Layne Energy Operating, LLC.  
**Lease Name:** Kammerer B&B 1-7  
Sec. 7 Twp. 30S Rng. 16E, Montgomery County  
**API:** 15-205-26275

<b>Shots per Foot</b>	<b>Perforation Record</b>	<b>Acid, Fracture, Shot, Cement Squeeze Record</b>	<b>Depth</b>
4	883-884.5, 770-771.5, 734.5-737	Bluejacket, Mineral, Croweburg-4400# 20/40 sand, 600 gal 15% HCl acid, 390 bbls wtr	734.5-884.5
4	713-714.5, 661.5-666.5, 645-648	Bevier, Mulky, Summit-6900# 20/40 sand 1000 gal 15% HCl acid, 530 bbls wtr	645-714.5

KCC  
SEP 05 2006  
CONFIDENTIAL

09/05/07

*Layne Energy, Inc.*

1900 Shawnee Mission Parkway, Mission Woods, Kansas 66205 Phone: (913) 748-3987 Fax: (913) 748-3970

September 5, 2006

Kansas Corporation Commission  
Oil & Gas Conservation Division  
130 S. Market, Room 2078  
Wichita, KS 67202

KCC  
SEP 05 2006  
CONFIDENTIAL

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 06 2006  
CONSERVATION DIVISION  
WICHITA, KS

Re: Well Completion Forms

To Whom It May Concern:

I have enclosed the amended ACO-1 forms and associated data for the following wells:

API # 15-205-26275  
Kammerer B&B 1-7


API # 15-205-26299  
Kammerer B&B 4-8

API # 15-205-26277  
Kammerer B&B 13-6

We respectfully request that all information submitted be kept confidential and per provision E-4 of K.A. R. 82-3-107, we request that the term of the confidentiality be extended by one year.

If you need additional information or have any questions or comments, please contact me at (913) 748-3987.

Best regards,

  
Brooke C. Maxfield

Enclosures

Cc Well File  
Field Office

