

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County. Sec. 17 Twp. 14S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE SE

Lease Owner Davis Bros.

Lease Name Ordway "C" Well No. 6

Office Address 510 McFarlin Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 4 1962

Application for plugging filed October 5 1962

Application for plugging approved October 5 1962


Plugging commenced October 5 1962

Plugging completed October 5 1962

Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				3 5/8"	179'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks

Filled hole with heavy drilling mud to 179', set plug, cemented with 20 sacks

Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks to bottom of cellar

**RECEIVED**  
STATE CORPORATION COMMISSION  
10-15-62  
OCT 15 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

L. J. Krause (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Krause

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 12th day of October, 1962

Paul C. Gardner  
Notary Public.

My commission expires January 3, 1966



DRILLER'S WELL LOG

Davis Bros.

Ordway "C" # 6 well located in  
C NE SE SE, Section 17-10S-18W  
Rooks County, Kansas

Commenced: September 24, 1962  
Completed: October 5, 1962  
Elevation: 2141 D. F.

Casing: 8 5/8" at 179'  
Cemented: w/125 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Top soil	0	35
Sand	35	40
Shale	40	155
Blue shale	155	181
Shale	181	260
Shale	260	450
Shale and shells	450	810
Sand	810	850
Shale w/Pyrite streaks	850	1020
Sand	1020	1090
Shale	1090	1524
Anhydrite	1524	1560
Red bed and shale	1560	1960
Shale	1960	2050
Shale and lime	2050	2130
Lime w/shale	2130	2360
Lime	2360	2440
Lime and shale	2440	2575
Shale w/lime	2575	2665
Shale and lime	2665	2745
Shale w/lime	2745	2855
Shale	2855	3117
Lime	3117	3604
Lime and chert	3604	3640
Conglomerate	3640	3682
Lime	3682	3712 T.D.

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before

TRANSIT CORPORATION

this 12th day of October, 1962

By *L. J. Krueger*

My commission expires January 3, 1966

*Paul E. Gathers*  
Notary Public

