


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec 17 Twp. 10S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Price Exploration Company
Lease Name Rempe "A" Well No. 1
Office Address 404 Oil Capital Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 5, 1969
Application for plugging filed (letter 5/8/69) May 5, 1969
Application for plugging approved May 5, 1969
Plugging commenced May 5, 1969
Plugging completed May 5, 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	234'	8-5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 720 feet. Set first plug @ 720 feet w/70 sacks cement.
Filled hole with heavy mud to 210 feet. Set second plug @ 210 feet w/20 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug at 40 feet w/10 sacks cement.
Pumped cement through drill pipe with pump truck. Job complete @ 1:15 PM, 5/5/69.

RECEIVED
STATE CORPORATION COMMISSION
5-9-69
MAY 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E E Hall
830 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of May, 1969

Barbara J. Layton
Barbara J. Layton Notary Public.

Feb. 1, 1972.



15-163-20200-000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

REMPE "A" #1
C NW SE SW Section 17-10S-18W
Rooks County, Kansas

Commenced: April 26, 1969
Completed: May 5, 1969

OPERATOR - Price Exploration Co.

DEPTH		FORMATION	REMARKS
From	To		
0	70	Top soil, clay and sand	
70	200	Shale and sand	
200	510	Shale	Ran 12 joints 8-5/8" casing, set @ 234' w/160 sacks cement.
510	1015	Shale and shells	
1015	1250	Sand	
1250	1545	Shale	
1545	1580	Anhydrite	
1580	1775	Shale w/shells	
1775	3390	Shale and lime	
3390	3475	Lime	
3475	3555	Lime and shale	
3555	3632	Lime	
3632	3680	Lime and shale	
3680	3750	Lime and chert	
3750	3790	Lime	
3790	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
WICHITA, KANSAS

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW SE SW Section 17-10S-18W, Rooks County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 8 day of May, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

