

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21,366-0000

LEASE NAME Andreson

WELL NUMBER C-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 20 TWP. 10 RGE. 18W (E) or (W)

COUNTY Rooks

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg. Russell, KS 67665

PHONE (913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed

Character of Well Oil

Plugging Commenced 1-21-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-25-94

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	277'	none
				5 1/2	3611'	586'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded bottom to 3195' & 5 sks cement. Shot @ 2100' & swedged in. Worked pipe, shot @ 1421', worked pipe. Pumped 125 sks w/250# hulls down to 850'. Shot @ 791' & 586', pulled 4 joints. Pumped 100 sks w/250# hulls & circulated to surface from 586'. Pulled rest of pipe, filled 8 5/8 casing to surface with 25 sks cement. 60/40 pos 10% gel. Plugging complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Contractor)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 1st (day of) February, 19 94



My Commission Expires:

FEB - 2 1994
2-2 '94

RECEIVED
STATE CORPORATION COMMISSION