

15-163-02609-000


STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 20 Twp. 10S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines 260' E. of C SE NE
Lease Owner Davis Bros.-Transit Corporation
Lease Name Ordway "E" Well No. 3
Office Address 1516 Liberty Bank Bldg., Oklahoma City 2, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 28 19 62
Application for plugging filed July 28 19 62
Application for plugging approved July 28 19 62
Plugging commenced July 28 19 62
Plugging completed July 28 19 62
Reason for abandonment of well or producing formation No production



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	180'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks
Filled hole with heavy drilling mud to 180', set plug, cemented with 20 sacks
Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
8-23-62
AUG 23 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (notary public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of August, 19 62

Paul E. Gubers

Notary Public.

My commission expires January 3, 1966



DRILLER'S WELL LOG

Davis Bros.-Transit Corporation

Ordway "Z" # 3 well located
260' E. of C SE NE, Sec. 20-10E-18N
Rooks County, Kansas

Commenced: July 19, 1962
Completed: July 28, 1962
Elevation: 2125' C.L.

Casings: 8 5/8" at 180'
Cemented: w/125 sacks

Formation	From	To
Surface soil, sand and Blue shale	0	183
Shale	183	275
Shale and shells	275	960
Sand	960	1130
Shale	1130	1492
Anhydrite	1492	1530
Shale and shells	1530	1620
Shale	1620	1900
Shale w/line streaks	1900	1995
Shale	1995	2040
Line w/shale	2040	2210
Line and shale	2210	2390
Line w/shale	2390	2735
Shale and line	2735	2845
Shale	2845	3105
Line	3105	3220
Line and shale	3220	3265
Line	3265	3340
Toronto	3340	3363
Lansing-Kansas City	3363	3430
Line	3430	3586 C.D.

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before me

this 2nd day of August, 1962

My commission expires January 3, 1966

TRANSIT CORPORATION

By L. J. Kruse

Paul E. Gathers
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1962
CONSERVATION DIVISION
Topeka, Kansas