

15-163-02472-0000

15-163-02472-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Roofs County. Sec. 21 Twp. 10S Rge. (E) 18 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$  NW $\frac{1}{4}$  SW $\frac{1}{4}$

Lease Owner. H H & B Drilling Co., Inc.

Lease Name. Ordway "A" Well No. 1

Office Address. 705 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed. 9-6-47 19. 47

Application for plugging filed. 9-6-47 19. 47

Application for plugging approved. 9-6-47 19. 47

Plugging commenced. 9-6-47 19. 47

Plugging completed. 9-6-47 19. 47

Reason for abandonment of well or producing formation. dry

If a producing well is abandoned, date of last production. --- 19. ---

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. C. L. Stough, Box 106, Hays, Kansas

Producing formation. none Depth to top. --- Bottom. --- Total Depth of Well. 5725 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>none</u>				<u>10-3/4" O.V. Tbd.</u>		
				<u>Surface</u>	<u>143'</u>	<u>none</u>
				<u>Oil string - none run</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Laid down drill pipe, plugged hole, filled hole with heavy mud, cemented bottom plug at bottom of surface - 150' with 15 sacks cement, cemented top plug with 10 sacks.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. H H & B Drilling Co., Inc.  
Address. 705 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Woods, SS. Richard Sedgwick

Jack H. Heathman (employee or owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack H. Heathman, Vice-Pres. H H & B Drilling Co.,  
705 Petroleum Bldg., Wichita 2, Kansas Inc.

SUBSCRIBED AND SWORN to before me this 11th day of September, 19. 47

Richard Hindery Notary Public.

My commission expires. July 2, 1949

21-6858-RS 2-47-6M

PLUGGING  
FILE SEC 21 T 10 R 18 W  
BOOK PAGE 131 LINE 25

15-2-47

ORLWAY "A" WELL NO. 1

Locations: Approx. Ctr. NE $\frac{1}{4}$  NW $\frac{1}{4}$  NW $\frac{1}{4}$  Sec. 21-10S-18W      Date Spudded: 8-21-47  
Rocks County, Kansas

Operators: H H & B Drilling Co., Inc.      Oil String Cemented: 9-5-47 plugged, none run

Contractor: H H & B Drilling Co., Inc.      Elevation: 2088 KB

Casing record: Surface Casing - 7 jts. or 143' of      Total Depth: 3725'  
10-3/4" 8 V Thd. cemented  
@ 150' w/collar in cellar  
w/80 sacks bulk cement.  
Oil String - none run  
Abandoned - 9-5-47

T O P S (KB)

Anhydrite	1410 (-1678)
Heebner	3292 (-1204)
Lansing	3338 (-1250)
Conglomerate	3590 (-1502)
Weathered Simpson	3668 (-1580)
Arbuckle	3697 (-1609)

L O G

(Figures indicate bottom of formation)

Clay and sand	0 to 40
Shale	155
Shale	350
Sand and shale	990
Sand	1090
Sand and shale	1410
Anhydrite	1450
Shale	1955
Lime and shale	2200
Lime	2250
Lime and shale	3115
Lime	3225
Lime and shale	3325
Lime	3575
Lime and Conglomerate	3605
Chert	3655
Conglomerate	3670
Chert and shale	3700
Lime	3725
Total Depth	3725'

The undersigned, H H & B DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H & B DRILLING CO., INC.

BY: John H. Hackman  
Vice-President

Subscribed and sworn to before me this 11th day of September 1947.

Richard Lindberg  
Notary Public

My commission expires: July 2, 1949.

**PLUGGING**  
FILE SEC. 21 T 10 R 18W  
BOOK PAGE 131 OF 25