

15-163-00897-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks County, Sec. 22 Twp. 10S Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW 1 SE NW

Lease Owner Davis Bros.

Lease Name Garvert "L" Well No. 1

Office Address 14 East Third Street, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed March 25, 19 59

Application for plugging filed March 25, 19 59

Application for plugging approved March 25, 19 59

Plugging commenced March 25, 19 59

Plugging completed March 25, 19 59

Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	162'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 600'; set plug, cemented with 20 sacks cement

Filled hole with heavy drilling mud to 150'; set plug, cemented with 1/2 sack hulls and 15 sacks cement

Filled hole with heavy drilling mud to 40'; set plug, cemented with 1/2 sack hulls and 10 sacks cement to bottom cellar

APR 30 1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 59

My commission expires May 17, 1962

Notary Public.

PLUGGING
FILE SEC. 22 T. 10. R. 18W
BOOK PAGE 30 LINE 13

RECEIVED
STATE OF KANSAS
DEPARTMENT OF REVENUE

DRILLER'S WELL LOG

APR 30 1959

Davis Bros. - Garvert "L" # 1 well located in
C NW SE NW Section 22-10S-18W,
Rooks County, Kansas

REVENUE DIVISION
Wichita, Kansas

Commenced: March 16, 1959
Completed: March 25, 1959
Elevation: 2137' KB

Casing 8 5/8" @ 162'
Cemented w/130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay	0	15
Rock	15	30
Sand	30	65
Shale	65	210
Shale and shells	210	1020
Sand	1020	1210
Shale and shells	1210	1440
Shale and red bed	1440	1504
Anhydrite	1504	1538
Shale	1538	2020
Shale and lime	2020	2045
Lime and shale	2045	2320
Fort Riley lime	2320	2420
Lime and shale	2420	2615
Shale w/lime streaks	2615	2760
Shale and lime	2760	2885
Shale and lime streaks	2885	3155
Shale and lime	3155	3205
Lime and shale streaks	3205	3275
Lime	3275	3615
Lime and chert	3615	3635
Conglomerate chert	3635	3716
Conglomerate, shale and lime	3716	3755
Arbuckle	3755	3760 TD

Summary of Formation

Anhydrite	1504'
Topeka	3115'
Heebner	3332'
Toronto	3352'
Lansing	3376'
Base of K.C.	3613'
Conglomerate	3633'
Simpson	3724'
Arbuckle	3744'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 14th. day of April, 1959.

TRANSIT CORPORATION

BY Paul G. Gathers

My Commission expires May 17, 1962.

Michael Dean
Notary Public

PLUGGING
FILE SEC 22 T. 10 R. 18W
BOOK PAGE 30 LINE 13