

15-163-02661-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

6-6-62  
JUN 6 1962

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks

Location: CNE SE Sec. 24 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 18

Name of Field: \_\_\_\_\_ Total Depth: 3647

I have this date completed supervision of plugging of:

Lease Name: Yohe Well No. 2-C

Operator's Full Name: Davis Bros

Complete Address: 1450 Maple St Russell, Kansas

Plugging Contractor: Barnes & Sons

Address: Russell, Kansas License No. 9

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 31 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 168' circulated with cement - 4 1/2" 3646' with 275 sax cement.

PB to 3633' Perf 3351'.

Sand to 3340', set 4 sax cement with dump bailer, pulled 2150' 4 1/2" to

550', circulated hole with heavy mud through 4 1/2" (21sax Gel), displaced

20 sax cement through 4 1/2" at 550', heavy mud to 180', displaced 20 sax

cement through 4 1/2" at 180', heavy mud to 30', cement 30' to 0'

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED

DATE 6/9/62

INV. NO. 5119-W