

15-163-00910-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-12-67
MAR 12 1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks
Location: NE NE SW Sec. 27 Twp. 10 Rge. _____ (E) _____ (W) 18
Name of Field: _____ Total Depth: 3686

I have this date completed supervision of plugging of:

Lease Name: Eilers Well No. A-1
Operator's Full Name: Davis Bros
Complete Address: 510 Mc Earlin Bldg Tulsa, Okla
Plugging Contractor Barnes & Sons Pipe Pulling
Address: Russell, Kansas License No. 9
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No X

If Yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 5 Month 3 Year 62

The above well was plugged as follows:

8 5/8" 176' circulated with cement - 4 1/2" 3683' with 260 sax cement - PB to 3525' - perforated 3349'
Filled with sand to 3320', set 4 sax cement with dump bailer, pulled 905' 4 1/2" to 650', circulated hole with heavy mud through 4 1/2" (30saxGel), displaced 20 sax cement through 4 1/2" at 550', heavy mud to 180', set 20 sax cement through 4 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: Harold Heers
Field Supervisor

Remarks:

INVOICED
DATE 3/19/62
INV. NO. 4681-W