

15-163-20043-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
8-14-67  
AUG 14 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name D. R. Lauck Oil Company

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name Dauwe Well No. 1

Location NE SE SE Sec. 30 Twp. 10 Rge. 18 (E) (W) X

County Rooks Total Depth 3682

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 5 P Day 10 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3682' 8 5/8 csg set at 210' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 90 sc cem.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/14/67

INV. NO. 6120-W