

15-163-20666-0000
R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

2-7-77
FEB 07 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,666 - 0000 (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 W. Douglas, Suite 550, Wichita, Kansas

Lease Name Bates Well No. 1

Location SW SE NW Sec. 28 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3670'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9:30 A Day 4 Month 2 Year 1977

The above well was plugged as follows:

RTD 3670' 8 5/8 csg set 244' cwc 175 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-7-77
INV. NO. 4597-W