

15-163-01888-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217RECEIVED  
STATE CORPORATION COMMISSION  
2-16-73  
FEB 16 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Andreson Well No. 1

Location NW NW NW Sec. 4 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3745'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2:15 P Day 15 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3745' 8 5/8 csg set at 203' cwc 150 sk.

5 1/2 csg set at 3744' cw 150 sk cmt.

Top of tubing fish at 2729'.

Set 5 1/2 wood plug at 2729' -poured sand to 2700 -dumped 5 sk cmt W/dump bailer. (2665-2700)

Dakato squeezed -cutoff and recovered 694' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug  
and pumped 100 sk "Halib-Light" cmt by HOWCO. PP 450 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/16/73  
INV. NO. 6986-4