

KANSAS

W
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Andreson Well No. 2

Location NW NE NW Sec. 4 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3727'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 1:15 P Day 15 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 3727' 8 5/8 csg set at 187' cwc: 115 sk.

5 1/2 csg set at 3726' cw 150 sk cmt.

5 1/2 csg perf. (3506-3510)

Filled 5 1/2 csg W/sd (3700-3727) dumped 3 sk cmt W/dump bailer. (3675-3700)

Set 5 1/2 wood plug at 3400' poured 10' sd -dumped 5 sk cmt W/dump bailer. (3350-3400)

Dakato squeezed -Cutoff and recovered 738' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls. released 8 5/8 plug

and pumped 100 sk "Halib.-Light" cmt by HOWCO. PP 500 lbs SI 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/16/73

INV. NO. 6987-W