

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
2-14-64
FEB 14 1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kans

Lease Name Joy Well No. 1

Location CW $\frac{1}{2}$ W $\frac{1}{2}$ SE Sec. 4 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3713

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 3PM Day 12 Month 2 Year 64

The Above well was plugged as follows:

8 5/8" 208' circulated with cement - 5 1/2" 3709' with 125 sax cement -
squeezed at 1155' with 200 sax cement - and squeezed at 1019' with 200
sax cement.

Sanded back to 3400', set 4 sax cement with dump bailer - pulled 855'
5 1/2" to 470', circulated hole with heavy gel mud (19 sax), displaced 20
sax cement through 5 1/2" at 470', heavy mud to 180', displaced 20 sax
cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/14/64
INV. NO. 86344-u

Signed: *Eldon Kelly*
Well Plugging Supervisor