

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 106-22 County: Rooks

Location: SE NE SW Sec. 4 Twp. 10 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3704

I have this date completed supervision of plugging of:

Lease Name: Ondrasek Well No. 1

Operator's Full Name: Petroleum Management

Complete Address: 1019 Central Bldg Wichita, Kans

Plugging Contractor: ~~Ondrasek~~ E & L Casing Pulling

Address: Great Bend, Kans License No. 249

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 8PM Day 8 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 225' circulated with cement - 5 1/2" 3690' with 125 sax cement
behind - squeezed at 1400' with 100 sax cement.

Pumped hole full heavy mud, pumped plug to 550', followed by 10 sax
cement, started 210' 5 1/2", displaced 20 sax cement through 5 1/2" at 200',
pulled 5 1/2" - filled hole with heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

Signed: *Edon Kelly*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 4 T 10 R 19 W
BOOK PAGE 106 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
7-19-58
JUL 19 1958
CONSERVATION DIVISION
Wichita, Kansas