

15-163-03010-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*Handwritten initials*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 106-23 County: Rooks

Location: NW NE SW Sec. 4 Twp. 10 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3702

I have this date completed supervision of plugging of:

Lease Name: Ondrasek Well No. 2

Operator's Full Name: Petroleum Management Inc.

Complete Address: 1019 Central Bldg Wichita, Kans

Plugging Contractor: E & L Casing Pulling

Address: Great Bend, Kans License No. 249

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 7 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 215' circulated with cement - 5 1/2" 3699' with 125 sax cement behind.

Filled with sand to ~~2747~~ 3680', set 4 sax cement with dump bailer,  
pulled 2747' 5 1/2" to 550', circulated hole with heavy mud (Gel),  
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200',  
displaced 20 sax cement through 5 1/2" at 200', heavy mud to 40', set  
cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.  
Mudding and cementing by E & L Company pump truck.

Signed: *[Signature]*  
Conservation Division Agent

Reviewed: *[Signature]*  
Field Supervisor

Remarks:

7-17-58

PLUGGING  
FILE SEC. 4 T. 10 R. 19W  
BOOK PAGE 106 LINE 23