

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
Phone: (303) 893-5090 Operator License #: 33476
Type of Well: D&A GAS KCC Pkt per CP2/3
The plugging proposal was approved on: 06/22/2009
by: Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [X] No
Producing Formation(s): List All (If needed attach another sheet)
Krider Depth to Top: 2574' Bottom: 2766' T.D. 2792'

API Number: 15 - 171-20118-00-00
Lease Name: Yager
Well Number: 1-19
Spot Location (QQQQ): - - C - NE
1320 Feet from [X] North / [ ] South Section Line
1320 Feet from [X] East / [ ] West Section Line
Sec. 19 Twp. 19 S. R. 31 [ ] East [X] West
County: Scott
Date Well Completed: 10/23/1976
Plugging Commenced: 06/24/2009
Plugging Completed: 06/26/2009

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Krider formation with Gas & Water content and casing records from 367' to 2790'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See attached.

RECEIVED

JUL 13 2009

KCC Pkt per CP2/3

99996 KCC WICHITA

Name of Plugging Contractor: Allied Cementing Company License #: 115725

Address: P.O. Box 31 Russell, KS

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC

State of Colorado County, Denver, ss.

Cassandra Parks (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Cassandra Parks

(Address) 420 17th St. Denver CO. 80202

SUBSCRIBED and SWORN TO before me this 9th day of July, 2009

Cynthia B. Kauer Notary Public My Commission Expires 7-1-2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature

## Yager 1-19 Plugging Record-Attachment

6/24/09-

MIRU Cheyenne well service DD unit. Lay down 15 jts 1" NUE 8rd tbg. Did not have fishing tool to fish 1" tbg. Latch onto 2-3/8" tbg. Release packer. Lay down 1 - 2', 1 - 10', 2 - 8' tbg subs, 3 jts 2-3/8" tbg. Approx 121' tbg - no drag while pulling. Latch onto 4th jt, pulled out 3' and hit tight spot. Work tubing to max pull of 55,000#, did not come loose. Work tbg back down hole 1 jt.

6/25/09-

Run 1-3/16" overshot on 13 jts 5/8" sucker rod down tbg, caught fish. Lay down rods, overshot, 74 jts 1" nue 8rd tbg & 2" x 1-1/2" x 12' RWT hollow rod pump. Latch onto 2-3/8" tbg and hook up water truck to annulus. Pump lease water by packer (3 bbl load to csg.)

Lay down the following:

86 jts 2-3/8" 8rd EUE tbg,

1 2-3/8" x 1.2' SN

1 4-1/2" x 2-3/8" x 2.5' Arrow tension packer

6-26-09-

Test tbg to 5500#, 84 jts tested good: 1 hole, 1 bad pin. RU Perf-Tech. Set CIBP @ 2550' KB. Hook up pressure truck to casing. Pumped 5 bbls, caught pressure to max of 500#, had slow drop in pressure to 200# in 1 minute. Ran cement bond log from 2550' to surface with the following results:

Fair cement bond 2550' to 1900' 50% bond  
good cement bond 1900' to 420' 100% bond  
Fair cement bond 100' to surface 50% bond

RU dump bailer, dump 2 sacks cement on plug at 2550'. TIH to 1600'. Mix 120 sacks 60/40 poz 4% gel, displace down tubing to 1600', cement circ to surface. Trip tbg out of hole. Displace 12 sacks 60/40 poz 4% gel down 8-5/8" - 4-1/2" annulus to max pressure of 300#. Displace 15 sacks 60/40 poz to top off 4-1/2". Job complete at 15:00 hours.

RECEIVED

JUL 13 2009

KCC WICHITA

# ALLIED CEMENTING CO., LLC. 044082

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Dakley

|  |                    |  |                            |            |                             |                          |                           |
|--|--------------------|--|----------------------------|------------|-----------------------------|--------------------------|---------------------------|
| DATE <u>6/26/09</u>                                      | SEC <u>9</u>       | TWP <u>19</u>                                | RANGE <u>31</u>            | CALLED OUT | ON LOCATION <u>11:30 Am</u> | JOB START <u>2:00 pm</u> | JOB FINISH <u>3:00 pm</u> |
| LEASE <u>Yeager</u>                                      | WELL # <u>1-19</u> | LOCATION <u>Scott City E TO Taos Rd, 55,</u> |                            |            | COUNTY <u>Scott</u>         | STATE <u>Ks</u>          |                           |
| <input checked="" type="radio"/> OLD OR NEW (Circle one) |                    |  | <u>1W, 1W, 1/4W, SINTO</u> |            |                             |                          |                           |

CONTRACTOR Cheyenne  
 TYPE OF JOB PTA  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 DEPTH \_\_\_\_\_  
 TUBING SIZE 2 3/8 DEPTH 1560'  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER Some  
 CEMENT AMOUNT ORDERED 300 SK, 60/40  
470 gal  
used 147 1/2 300 16 Halls On Side  
 COMMON 88 @ 15 45 1359 60  
 POZMIX 59 @ 8 00 472 00  
 GEL 5 @ 20 80 104 00  
 CHLORIDE @ \_\_\_\_\_  
 ASC @ \_\_\_\_\_

EQUIPMENT

PUMP TRUCK CEMENTER Alan  
 # 422 HELPER Wayne  
 BULK TRUCK # 399 DRIVER Terry  
 BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED  
 JUL 13 2009  
 KCC WICHITA

C.S. Halls 5 SK @ 31 85 159 25  
 HANDLING 157 @ 2 40 376 80  
 MILEAGE 104 SK/mile @ \_\_\_\_\_ 863 00  
 TOTAL 3335 15

REMARKS:  
Mix 120SK, 60/40/40 gal Down 2 3/8  
Tubing @ 1560 Circ Gate TO Surface,  
Pull All Tubing, Mix 12 SKS Down  
B. Side TO 300' PST, Mix 15SKS TO  
TO TOP OFF 4 1/2,  
 Thank You  
Alan, Wayne, Terry

SERVICE

DEPTH OF JOB 1560'  
 PUMP TRUCK CHARGE \_\_\_\_\_ 900 00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 55 @ 7 00 385 00  
 MANIFOLD @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL 1285 00

CHARGE TO: FIML  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

\_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 TOTAL \_\_\_\_\_

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME EL Abacrombie  
 SIGNATURE [Signature]

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS