

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC  
Address: 410 17th Street Ste. 900  
Phone: (303) 893-5090 Operator License #: 33476  
Type of Well: Gas D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 06/22/2009 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Krider Depth to Top: 2776' Bottom: 2784' T.D. 4712'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 171-20538-0000  
Lease Name: Dearden  
Well Number: 1-7  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - SE - SE  
500 Feet from  North /  South Section Line  
400 Feet from  East /  West Section Line  
Sec. 7 Twp. 1619 S. R. 31  East  West  
County: Scott  
Date Well Completed: 10/1999  
Plugging Commenced: 06/24/09  
Plugging Completed: 06/24/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Krider	Gas and water	0	262'	8-5/8"	10/1999	
		0	2964'	4/1/2"	10/1999	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU DD unit. Release gas pressure on annulus. Unseat pump. Lay down 1-2'; 1-4' pony sub; 112-5/8" plain rod; & 2" x 1-1/2" x 10' RWAQ pump.  
Lay down 90 jts 2-3/8" 8rd eue tubing. RU Allied Cementing. Plug well as follows. Mix 15 sxs 60/40 poz, 4% gel, displace down 8-5/8"x 4-1/2" annulus to 300#-held. Mix 200# hulls, 190 sxs 60/40 poz 4% gel, displace down 4-1/2" csg to 500#-held. Plugging complete @ 2:30 pm 6-24-09.

Witnessed by Ken Jehlik-KCC.

Name of Plugging Contractor: Allied Cementing Company License #: 118725 99996 RECEIVED  
Address: P.O. Box 31 Russell, KS JUL 13 2009  
Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC  
State of Colorado County, Denver, ss. KCC WICHITA

Cassandra Parks (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Cassandra Parks

(Address) 410 17th St. #900 Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 29<sup>th</sup> day of June, 2009  
Christopher B. Lauer My Commission Expires: 7-7-2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# ALLIED CEMENTING CO., LLC. 043555

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Orley KS

DATE <u>6-24-09</u>	SEC <u>7</u>	TWP. <u>19S</u>	RANGE <u>31W</u>	CALLED OUT	ON LOCATION <u>1:00pm</u>	JOB START <u>2:00pm</u>	JOB FINISH <u>2:30pm</u>
Dewden LEASE		WELL# <u>1-7</u>	LOCATION <u>Scotchy C-Taos Rd</u>		COUNTY <u>Scot</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Cheyenne Well Service OWNER FIML

TYPE OF JOB AWP

HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH <u>2964'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS. <u>2776-2784</u>	
DISPLACEMENT	

CEMENT  
AMOUNT ORDERED 200 60/40  
490 cel (used 195)  
200# hulls on side

COMMON	<u>117</u>	@ <u>15.45</u>	<u>1807.65</u>
POZMIX	<u>78</u>	@ <u>8.00</u>	<u>624.00</u>
GEL	<u>7</u>	@ <u>20.70</u>	<u>145.50</u>
CHLORIDE		@	
ASC		@	

Hulls RECEIVED @ 31.85 127.40

JUL 13 2009

KCC WICHITA

HANDLING	<u>211</u>	@ <u>2.40</u>	<u>506.40</u>
MILEAGE	<u>1045ky mile</u>		<u>1160.50</u>
TOTAL			<u>4371.55</u>

**EQUIPMENT**

PUMP TRUCK	CEMENTER <u>Fuzzy</u>
# <u>431</u>	HELPER <u>Kelly</u>
BULK TRUCK	
# <u>347</u>	DRIVER <u>Terry</u>
BULK TRUCK	
#	DRIVER

**REMARKS:**

Mix 155Ks down annulus  
press to 300# + release

Mix 180 Ks cement + 200#  
hulls down 4 1/2 csg. Press  
to 500# + hold wash up  
release press

Job complete 2:30pm  
THANKS Fuzzy & crew

CHARGE TO: FIML NAT Resources

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB	<u>2784'</u>
PUMP TRUCK CHARGE	<u>1185.00</u>
EXTRA FOOTAGE	@
MILEAGE	<u>55</u> @ <u>7.00</u> <u>385.00</u>
MANIFOLD	@
	@
	@

TOTAL 1570.00

**PLUG & FLOAT EQUIPMENT**

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME EC Abeworamba

SIGNATURE [Signature]

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS