

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 07/13/2009 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 4246' Bottom: 4250' T.D. 4618'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 101 - ~~24528~~ - 0000
Lease Name: Schwartz
Well Number: 1
Spot Location (QQQQ): approx - NW - SE - SW
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 25 Twp. 19 S. R. 28 East West
County: Lane
Date Well Completed: 11/27/1989
Plugging Commenced: 07/08/2009
Plugging Completed: 07/13/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & Water	4246'	4250'	8.625"	233	-0-
				4.50"	4637	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Pulled tubing out of hole. Pumped 40 sx 60/40 Pozmix cement + 4% Gel, 150# hulls, pumped 12 sx Gel & 24 barrels fresh water spacer, & pumped 150 sx 60/40 Pozmix cement w/4% gel down 4.50" casing to 200#, circulated to surface up braden head. Shut in 4.50" casing and braden head @ 200#. Plugging complete at 10:00 a.m. on 07/13/2009 witnessed and approved by Mike Maier w/ the KCC.

Name of Plugging Contractor: Allied Cementing License #: 99996 KANSAS CORPORATION COMMISSION
Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.

John Niernberger - employee of Ritchie Exploration, Inc (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 783188 Wichita, KS 67278-3188



and SWORN TO before me this 27th day of July, 20 09
Ronda Messer My Commission Expires: 5/7/12
Notary Public

JUL 28 2009
RECEIVED

[Handwritten initials]

ALLIED CEMENTING CO., LLC. 044092

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Dakka, KS

DATE <u>7/13/09</u>	SEC <u>25</u>	TWP. <u>19</u>	RANGE <u>28</u>	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>9:00</u>	JOB FINISH <u>10:00</u>
LEASE <u>Schwartz</u>	WELL #	LOCATION <u>Dighton E to Quanton Rd</u>			COUNTY <u>Lane</u>	STATE <u>KS</u>	
<input checked="" type="checkbox"/> OLD <input type="checkbox"/> NEW (Circle one)			<u>570 70 Rd 4 1/2 W points</u>				

CONTRACTOR none

TYPE OF JOB PTA

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. 4200

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 190 SKs 60/40
4000 gel

EQUIPMENT

PUMP TRUCK CEMENTER Wayne Alan

19275400 HELPER Wayne

BULK TRUCK # 394 DRIVER Wayne - GB

BULK TRUCK # 399 DRIVER Alvin - GB

COMMON <u>115</u>	@ <u>13.65</u>	<u>1569.75</u>
POZMIX <u>75</u>	@ <u>7.60</u>	<u>570.00</u>
GEL <u>19</u>	@ <u>20.40</u>	<u>387.60</u>
CHLORIDE	@	
ASC	@	
<u>15016 Halls - 3 SKs</u>	@ <u>31.20</u>	<u>93.90</u>
HANDLING <u>200 SKs</u>	@ <u>2.10</u>	<u>420.00</u>
MILEAGE <u>10.4 SK/mile</u>		<u>630.00</u>
TOTAL		<u>3702.95</u>

REMARKS:
mix 40 SKs 60/40 4000, mix 15016 Halls
mix 12 SKs gel, mix 150 SKs 60/40
4000 gel, 0 TO 200 PST
B-side - Full

Thank You
Alan, Wayne, Wayne, Alvin

CHARGE TO: Ritchie Exploration

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>4250 FT</u>
PUMP TRUCK CHARGE	<u>1890.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>30</u>	@ <u>7.00</u> <u>210.00</u>
MANIFOLD	@
TOTAL <u>1380.00</u>	

KANSAS CORPORATION COMMISSION
PLUG & FLOAT EQUIPMENT

JUL 28 2009
RECEIVED

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Gary Rowe

SIGNATURE Gary Rowe

SALES TAX (If Any)	_____
TOTAL CHARGES	_____
DISCOUNT	_____ IF PAID IN 30 DAYS

[Signature]