

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 07/13/2009 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Altamont B1 Depth to Top: 4366' Bottom: 4370' T.D. 4572'
Pleasanton Depth to Top: 4301' Bottom: 4304' T.D. 4572'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 171-20581 - 0002
Lease Name: Pember 11D
Well Number: 1
Spot Location (QQQQ): approx - N/2 - SE - SE
1100 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 11 Twp. 17 S. R. 31 East West
County: Scott
Date Well Completed: 10/01/2003
Plugging Commenced: 07/09/2009
Plugging Completed: 07/13/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Altamont B1	Oil & Water	4366'	4370'	8.625"	316	-0-
Pleasanton	Oil & Water	4301'	4304'	5.50"	4620'	-0-


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled tubing out of hole. Pumped 40 sx 60/40 Pozmix cement + 4% Gel, 150# hulls, pumped 16 sx Gel & 32 barrels fresh water spacer, & pumped 275 sx 60/40 Pozmix cement w/4% gel down 5.50" casing, shut in at 500#. Pumped 10 sx 60/40 Pozmix cement w/ 4% Gel, down 8.625" casing to 300#, shut in. Plugging complete at 3:30 p.m. on 07/13/2009 witnessed and approved by Mike Maier w/ the KCC.

Name of Plugging Contractor: Allied Cementing License #: 99996 KANSAS CORPORATION COMMISSION
Address: P. O. Box 31 Russell, KS 67665
Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) P. O. Box 783188 Wichita, KS 67278-3188



SUBSCRIBED and SWORN TO before me this 27th day of July, 20 09
Ronda Messer My Commission Expires: 5/7/12
Notary Public

JUL 28 2009
RECEIVED

PM

ALLIED CEMENTING CO., LLC. 044094

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: 2000/1/1

DATE <u>7/13/09</u>	SEC. <u>11</u>	TWP. <u>17S</u>	RANGE <u>31W</u>	CALLED OUT	ON LOCATION <u>2:30</u>	JOB START <u>2:30</u>	JOB FINISH <u>3:30</u>
LEASE <u>Pember</u>	WELL # <u>11 D #1</u>	LOCATION <u>Manning Rd + Hwy 4 IE</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>15 W/INTO</u>			

CONTRACTOR None
 TYPE OF JOB PTA
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT AMOUNT ORDERED _____
325 SKs 60/40 470 gal
 COMMON 195 @ 13.65 2661.75
 POZMIX 130 @ 7.00 910.00
 GEL 27 @ 20.40 550.80
 CHLORIDE @ _____
 ASC @ _____
15016 Halls - 3 SKs @ 31.20 932.00
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 HANDLING 355 @ 2.10 745.50
 MILEAGE 100 SK/mile @ _____ 1775.00
 TOTAL 6814.95

EQUIPMENT

PUMP TRUCK CEMENTER Alan
 # 422 HELPER Wayne
 BULK TRUCK _____
 # 399 DRIVER Alvin
 BULK TRUCK _____
 # _____ DRIVER _____

REMARKS:
Mix 40 SKs w/ 15016 Halls Down 5 1/2"
Mix 10 SKs gel w/ 32 Halls H₂O spacer
Mix 225 SKs Down 9 1/2" to 560 PSI
Mix 10 SKs Down on B. Side to 300 PSI

*Thank You
Alan, Wayne, Alvin*

CHARGE TO: Ritchie Exploration
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____ 4100
 PUMP TRUCK CHARGE _____ 447.00
 EXTRA FOOTAGE @ _____
 MILEAGE 50 @ 7.00 350.00
 MANIFOLD @ _____
 @ _____
 @ _____
 TOTAL 797.00

KANSAS CORPORATION COMMISSION PLUG & FLOAT EQUIPMENT

JUL 28 2009
RECEIVED

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Gary Rowe
 SIGNATURE Gary Rowe

TOTAL _____
 SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

[Signature]