



Operator Name: - R&B Oil & Gas Lease Name: Trantham Well #: 2  
 Sec. 27 Twp. 32 S. R. 10  East  West County: Barber County, Kansas

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets)

Samples Sent to Geological Survey  Yes  No

Cores Taken  Yes  No

Electric Log Run  Yes  No  
 (Submit Copy)

List All E. Logs Run:

Dual Compensated Porosity  
 Dual Induction  
 Sonic Cement Bond

Log Formation (Top), Depth and Datum  Sample  
 Name Top Datum  
 Miss 4366 -2916

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24#	224'	60/40	200	3%cc 2%gel
Production	7-7/8"	5-1/2"	14#	4528'	ASC	125	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	4390-4420	1500 gal 7 1/2% Acid	
		Frac 340 sxs 16/30 Sand	
		60 sxs CRC 16/30 Sand	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-7/8"	4358		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.		Producing Method			
9-29-05		<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil 16 Bbls.	Gas 130 Mcf	Water 150 Bbls.	Gas-Oil Ratio 8.125 - 1	Gravity 30

Disposition of Gas  Vented  Sold  Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled  Other (Specify) \_\_\_\_\_

Production Interval \_\_\_\_\_

# ALLIED CEMENTING CO., INC. 20885

SHIP TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
MEDICINE LODGE

DATE <u>9-1-05</u>	SEC. <u>27</u>	TWP. <u>32S</u>	RANGE <u>10W</u>	CALLED OUT <u>1:30 pm</u>	ON LOCATION <u>3:00 pm</u>	JOB START <u>4:30 pm</u>	JOB FINISH <u>5:00 pm</u>
TRAFFHAM LEASE		WELL # <u>2</u>	LOCATION <u>OLD 160 &amp; HAZELTON RD, 1/2 C.</u>		COUNTY <u>SARASOTA</u>	STATE <u>KS</u>	
OLD OR <u>(NEW)</u> (Circle one)			S/INTO				

CONTRACTOR DUKE #2  
 TYPE OF JOB SURFACE CASING  
 HOLE SIZE 12 1/4" T.D. 225'  
 CASING SIZE 8 5/8" DEPTH 224'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2" DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 300 MINIMUM 50  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 15'  
 CEMENT LEFT IN CSG. 15'  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 13 1/4 bbl. FRESH WATER

OWNER ADD OIL & GAS  
 CEMENT  
 AMOUNT ORDERED 200.5x 60:40:2 + 3% CC, 30" SUGAR

EQUIPMENT  
 PUMP TRUCK CEMENTER BILL M.  
 # 368 HELPER DWAYNE W.  
 BULK TRUCK  
 # 353 DRIVER JERRY C.  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

COMMON	<u>120</u>	<u>A</u>	@	<u>8.70</u>	<u>1044.00</u>
POZMIX	<u>80</u>		@	<u>4.70</u>	<u>376.00</u>
GEL	<u>3</u>		@	<u>14.00</u>	<u>42.00</u>
CHLORIDE	<u>7</u>		@	<u>38.00</u>	<u>266.00</u>
ASC			@		
<u>Sugar 30"</u>	<u>30</u>	<u>#</u>	@	<u>1.00</u>	<u>30.00</u>
			@		
			@		
			@		
			@		
HANDLING	<u>210</u>		@	<u>1.60</u>	<u>336.00</u>
MILEAGE	<u>10</u>	<u>x 210</u>	<u>x .06</u>		<u>180.00</u>
				<u>Min Chg</u>	<u>TOTAL 2274.00</u>

REMARKS:

PIPE ON BOTTOM, BREAK CIRCULATION  
PUMP 200.5x 60:40:2 + 3% CC, STOP PUMPS,  
RELEASE PLUG, START DISPLACEMENT, SEE  
LIFT, SEAL RATE, SHUT DOWN AT 13 1/4 bbl.  
DISPLACEMENT, SHUT IN WITH 100 lbs.

SERVICE

DEPTH OF JOB 224'  
 PUMP TRUCK CHARGE \_\_\_\_\_ 670.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 10 @ 5.00 50.00  
 MANIFOLD HEAD RENT @ 75.00 75.00  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

CHARGE TO: ADD OIL & GAS.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL 795.00

PLUG & FLOAT EQUIPMENT

8 5/8" WOODEN PLUG 1 @ 55.00 55.00  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

TOTAL 55.00

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE John Armbruster

JOHN ARMBRUSTER  
 PRINTED NAME

RECEIVED  
 OCT 20 2005  
 KCC WICHITA

# ALLIED CEMENTING CO., INC.

16378

PO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge KS*

DATE <i>09 08 05</i>	SEC. <i>27</i>	TWP. <i>32 S</i>	RANGE <i>10 W</i>	CALLED OUT <i>06 00 Am</i>	ON LOCATION <i>8 30 Am</i>	JOB START <i>11 10 Am</i>	JOB FINISH <i>12 20 pm</i>
LEASEE <i>Trantham</i> WELL# <i>2</i>		LOCATION <i>Sharon, KS old 160 &amp; Hazelton</i>			COUNTY <i>Barber</i>	STATE <i>KS</i>	
OLD OR <u>NEW</u> (Circle one)			<i>Rd, 1/2 E, sp into</i>				

CONTRACTOR *Duke #2*  
 TYPE OF JOB *Long string Production Casing*  
 HOLE SIZE *7 7/8* T.D. *4530*  
 CASING SIZE *5 1/2* DEPTH *4532*  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX *1350* MINIMUM *100*  
 MEAS. LINE SHOE JOINT *30.70*  
 CEMENT LEFT IN CSG. *30.70*  
 PERFS.  
 DISPLACEMENT *109 3/4 Bbls 2% KCL Water*

OWNER *R & B oil and gas*  
 CEMENT  
 AMOUNT ORDERED *50 sx 60:40:6 + 4% sms / 125 sx ASC + 5# Kolseal + .5% FL 160 500 gal mud clean / 13 gal clapano*

EQUIPMENT  
 PUMP TRUCK CEMENTER *D. FELIO*  
 # *240* HELPER *West, Dwayne*  
 BULK TRUCK  
 # *356* DRIVER *S. Kramer*  
 BULK TRUCK  
 # DRIVER

COMMON	<i>30</i>	<i>A</i>	@	<i>8.70</i>	<i>261.00</i>
POZMIX	<i>20</i>		@	<i>4.70</i>	<i>94.00</i>
GEL	<i>3</i>		@	<i>14.00</i>	<i>42.00</i>
CHLORIDE			@		
ASC	<i>125</i>		@	<i>10.75</i>	<i>1343.75</i>
<i>Kol Seal</i>	<i>625 #</i>		@	<i>.60</i>	<i>375.00</i>
<i>FL-160</i>	<i>59 #</i>		@	<i>8.70</i>	<i>513.30</i>
<i>Mud Clean</i>	<i>500 gal</i>		@	<i>1.00</i>	<i>500.00</i>
<i>Clapano</i>	<i>13 gal</i>		@	<i>22.90</i>	<i>297.70</i>
<i>Sodium Metasilicate</i>	<i>172 #</i>		@	<i>1.60</i>	<i>275.20</i>
			@		
			@		
HANDLING	<i>218</i>		@	<i>1.60</i>	<i>348.80</i>
MILEAGE	<i>10 x 218 x .06</i>				<i>180.00</i>
	<i>Min chg</i>				<i>TOTAL 4230.75</i>

REMARKS:

*Pipe on Bottom, Break Circ. Pump 20 Bbls 2% KCL follow with 3 Bbls Fresh H<sub>2</sub>O & 10 Bbls mud clean & 3 Bbls Fresh, Plug Rat & mouse hole with 25 sx 60:40:6 + 4% sms Run 25 sx 60:40:6 + 4% sms as scavenger cement, Pump 125 sx ASC + 5# Kolseal + .5% FL 160, Stop, wash pumps, Release Plug, start disp. with 2% KCL water, Reciprocate Pipe, Steel lift at 78 Bbls 2% water at 80 Bbls stop recip. at 100 Bbls slow rate at 100, Bump plug to 1350 psi at 109 3/4 Bbls total 2% KCL water Disp. Release PSI Float held*  
 CHARGE TO: *Rand B oil & gas*

SERVICE

DEPTH OF JOB	<i>4532'</i>		
PUMP TRUCK CHARGE			<i>1435.00</i>
EXTRA FOOTAGE		@	
MILEAGE <i>10</i>		@	<i>5.00 50.00</i>
<i>Head rental</i>		@	<i>75.00 75.00</i>
		@	
		@	

TOTAL *1560.00*

STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

*5 1/2"*

MANIFOLD		@	
<i>1-TRP</i>		@	<i>60.00 60.00</i>
<i>1-Guide Shoe</i>		@	<i>160.00 160.00</i>
<i>6-Centralizers</i>		@	<i>50.00 300.00</i>
<i>1-AFH Insert</i>		@	<i>235.00 235.00</i>

TOTAL *755.00*

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING

SIGNATURE *Tim Pierce*

TAX \_\_\_\_\_  
 TOTAL CHARGE ~~\_\_\_\_\_~~  
 DISCOUNT ~~\_\_\_\_\_~~ IF PAID IN 30 DAYS

*TIM PIERCE*  
 PRINTED NAME