

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20283-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 13-13S-21W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: KUHN Well #: 1  
County: TREGO Total Vertical Depth: 3893 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220	0	w/140 sxs cmt
PROD	5.5	3887	0	w/60 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2009 9:00 AM  
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE  
Proposal Rcvd. from: DAVID FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Shoot perfs at 850' and 200'.  
Hole is bridged off at 1160' - can not go through.

CONTROL NUMBER: 20090078-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2009 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1160' - pumped 130 sxs cement.  
Pulled tubing to 580' - pumped 60 sxs cement - good circulation of cement.  
Pulled tubing out - tied onto 5 1/2" - pumped 140 sxs cement - good circulation out backside.  
Shut in at 200# P.S.I.

Perfs:

RECEIVED  
JUL 15 2009  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3404.

Plugged through: TBG

District: 04

Signed

Marvin Mills  
(TECHNICIAN)

CM

Form CP-2/3

JUL 10 2009

PK

GRAVES DRILLING CO.

#1 KUHN

13-13-21W  
SE NW SE

505 UNION CENTER, WICHITA, KS.  
CONTR DRELLING OIL, INC.

CTY TREGO

GEOL FRED STUMP

FIELD HERBERT

E 2199 KB C 6/25/74 CARD 8/15/74 IP P 85 BOPD + TR WTR

CONG OH 3887-93

API 15-195-20,283

	+	+
	+	+
	+	+

LOG	TOPS	DEPTH	DATUM
TOP		3215	-1016
HEEB		3464	-1265
LANS		3502	-1303
BKC		3746	-1547
MARM		3799	-1600
CONG		3844	-1645
CONG SD		3884	-1685
LTD		3891	-1692
RTD		3893	-1694

8-5/8" 220/140sx, 5 1/2" 3887/60sx

DST (1) 3618-3650/20-30-30-30, REC 15' M  
W/SSO, BHP 73-63#, FP 40-54#

DST (2) 3648-3695/20-30-30-30, REC 20'  
M, NS, BHP 78-78#, FP 78-84#

DST (3) 3887-3893/10-30-60-30, REC  
1265' CO & 120' MDY O, NW, BHP 1123-  
1000#, FP 116-232#

MICT - CO & SWB 33BOPM/4HRS, POP, NAT

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS