

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07294-00-00
Spot: NENESE Sec/Twnshp/Rge: 7-18S-13W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: SMITH W O Well #: 7
County: BARTON Total Vertical Depth: 3327 feet

Operator License No.: 4424
Op Name: SMOKEY VALLEY RESOURCES
Address: RR 3, BOX 63
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	775	0	w/unknown sxs cmt
PROD	5.5	3321	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/30/1999 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 400# hulls.
This well was plugged in 1999. It was found in a TA file review. CP 2/3 was never completed. Cement ticket #2639 was used to complete this CP 2/3.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%) NOT WITNESSED
Date/Time Plugging Completed: 07/30/1999 5:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Plugged off bottom with sand to 3300' and 5 sxs cement. Shot pipe at 2030'.
Pulled up to 1525' and pumped 105 sxs cement with 300# hulls.
Pulled up to 800' - pumped 40 sxs cement with 100# hulls.
Pulled up to 250' and circulated cement to surface.

Perfs:

KANSAS CORPORATION COMMISSION
JUL 16 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #2639.

Plugged through: CSG

District: 04

Signed Approved per cement ticket - Cam Morris
(TECHNICIAN)

14

MORRIS SITRIN & SOHIO PET #7 W O SMITH 7-18-13W NE NE SE 5?

Contr. MURFIN DRILLING BARTON County

E. 1829 Comm Comp. 4-9-54 IP 315 BOPD

Tops	Depth	Datum
ANH	772	1057
HEEB	3011	-1182
LANS	3103	-1274
ARB	3319	-1490
TD	3327	-1498

Casing
 8" 775
 5" 33321
 DST 2232-58/1/2 HR, 10' MUD,
 SSO, BHP 0#
 DD 3327: SWB 1/2 BOPH: ACID
 750: SWB 20 BOPH/6 HR: 105
 80/8 HR

BOYD POOL

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS

Vertical text on the left side of the page, possibly a well name or reference number.