

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21727-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 26-14S-16W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ROBBEN Well #: 1
County: ELLIS Total Vertical Depth: 3370 feet

Operator License No.: 32875
Op Name: CWB - CO, A GENERAL PARTNERSHIP
Address: 40837 BEAR CRK RD
SPRINGVILLE, CA 93265

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	924	0	w/450 sxs cmt
PROD	4.5	3369	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: CWB - CO, A GENERAL PARTNERS Phone: (559) 539-2505

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 15 sxs gel spacer - 500# hulls.
Left packer in the hole at 3200'.
109.53

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2009 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 915'.
Ran tubing to 2976'. Allied pumped 10 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 730'. Allied pumped 50 sxs cement with 200# hulls - cwc.
PTOH. Topped off 4 1/2" casing with 20 sxs cement.
Max. P.S.I. 400#. Backside pumped 5 sxs.
Max. P.S.I. 350#. S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3075	3216		

INVOICED

DATE 7-29-09
INV. NO. 2010060059

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED CM

JUN 05 2009

Form CP-2/3

KCC WICHITA

JUN 02 2009

PPT

R. P. NIXON OPERATIONS
 207 W. 12TH STREET
 HAYS, KS 67601

CONTR BUFFALO DRLG., INC. #1 ROBBEN
 GEOL _____ CITY ELLIS

26-14-16W
 SW SW SE

E 1828 KB CM 9/5/79 CARD ISSUED 2/14/80 FIELD DREILING SE EXT(1/8 E)
 API 15-051-21,727 IP P 40 BOPD & WTR

LKC 3075-3216 OA

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
SC		920	+ 908
B SC		957	+ 871
TOP		2803	- 975
HEEB		3021	-1193
TOR		3039	-1211
LKC		3073	-1245
B KC		3301	-1473
PENN CONG		3314	-1486
ARB		3359	-1531
TD		3370	-1542

'8-5/8" 924/450sx, 4 1/2" 3369
 DST (1) 3126-3172/15-30-60-30, REC
 180' HGMCO, SIP 672-641#, FP 72-
 82/83-83#
 DST (3) 3297-3370/15-30-60-30, REC
 870' VSGCW, SIP 1146-1135#, FP
 114-176/238-455#
 MICT - CO, PF 3214-3216, AC 750 GAL,
 PF 1/3144, 1/3155, 1/3164, AC 2500
 GAL, PF 3075-3078, AC 750 GAL, SWB
 8 BFPH (90% OIL)/2HRS, ALL ZONES,
 600 OFF BOTTOM, POP, P 40 BOPD & WTR

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

15-PL-1
 26-14-16W