

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20488-00-00
Spot: NW Sec/Twnshp/Rge: 35-28S-8W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: RAMSEY 0 M Well #: 1
County: KINGMAN Total Vertical Depth: 4118 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DR STE 204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4065		
SURF	8.625	208		225 SX
PROD	4.5	4115		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DAVID MAYFIELD Company: KLIMA OIL Phone: (620) 793-8888

Proposed Plugging Method: PER KCC RULES
133.84

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/14/2009 11:45 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

WIRELINE SET CIBP AT 4065' DUMPED 2 SX OF CEMENT ON TOP OF PLUG. THEN LOADED HOLE AND RAN BOND LOG, BECAUSE PRODUCTION CASING HAD BEEN CEMENTED IN. LOG SHOWED CEMENT ON BACKSIDE OF 4.5" FROM SURFACE TO 856'. SHOT PERFS AT 1200' TRIED TO PUMP INTO, AT 900 LBS STILL WOULD NOT TAKE FLUID, SHOT ANOTHER SET OF PERFS AT 1500' SAME RESULTS AS ABOVE, SHOT PERFS AT 1900' TRIED TO PUMP INTO, STILL NOT TAKING VERY MUCH FLUID AT 900 LBS. RAN TUBING INTO 1961' SPOTTED 75 SX OF CEMENT, SQUEEZED UNDER PRESSURE. CAME BACK AND TAGGED AT 922' CIRCULATED TO SURFACE WITH 95 SX OF CEMENT. CAME BACK ON THE 14TH OF MAY AND CUT HEAD OFF, CEMENT 3' BELOW HEAD, OK TO CLOSE.

Perfs:

INVOICED
DATE 7-29-09
INV. NO. 2010060060

KANSAS CORPORATION COMMISSION


JUN 04 2009
RECEIVED

Remarks: ALLIED CEMENTING OUT OF GREAT BEND. TICKET #34336

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

