

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20865-00-01
Spot: S2NESW Sec/Twnshp/Rge: 31-27S-4W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BARTHOLOMEW UNIT Well #: TR 14-11
County: SEDGWICK Total Vertical Depth: 4134 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N MARKET STE 1230
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		115 SX
PROD	5.5	3944	2820	200 SX

134.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31714 Plug Co. Name: NOVY OIL & GAS, INC.
Proposal Rcvd. from: KIRK GLENN Company: NOVY OIL & GAS Phone: (316) 265-4651

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/20/2009 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3700' TOPPED WITH 5 SX OF CEMENT. SHOT CASING LOOSE AT 2820' PULLED CASING TO 807' SPOTTED 35 SX OF COMMON CEMENT WITH 3% C.C. TAGGED AT 750' PULLED CASING TO 360' CIRCULATED TO SURFACE WITH 170 SX OF COMMON CEMENT. FELL BACK TO 39' TOPPED OFF WITH 15 SX OF COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
3746	3750	CSG	

KANSAS CORPORATION COMMISSION
JUN 04 2009
RECEIVED
INVOICED
DATE 7-29-09
INV. NO. 2010060061

Remarks: ALLIED CEMENTING CO OUT OF MEDICINE LODGE. COMMON AND C.C. USED TICKET #32325

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)

JK

AKT