

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04469-00-00
Spot: SWNE Sec/Twnshp/Rge: 7-19S-11W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: KRAMP Well #: 2
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W 47TH ST STE 412
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3145		
SURF	8.625	0	0	UNK
PROD	5.5	3364	0	UNK

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2009 12:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 435 sxs 60/40 pozmix - 4% gel - 12 sxs gel spacer - 500# hulls.
CIBP at 3145'. Perf Tech perfed at 300' - 550' - 1320'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2009 9:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

05/12/2009 - Mike's Testing RIH with tubing to 3100'.
Copeland rigged to tubing and pumped 12 sxs gel spacer - followed with 60 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1350'. Copeland rigged to tubing and pumped 75 sxs cement with 150# hulls mixed in.
Pulled tubing t 600'. Copeland rigged to tubing and pumped 175 sxs cement with 150# hulls mixed in - cement did not circulate.
Rigged to 8 5/8" and pumped 5 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Pulled tubing - left set overnight.
05/13/2009 - RIH to 300' - tagged cement and pumped 110 sxs to circulate cement.
Pulled tubing - topped off hole with 10 sxs cement. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3100	3129		

INVOICED
DATE 7-29-09
INV. NO. 2010060062

KANSAS CORPORATION COMMISSION
JUN 03 2009
RECEIVED

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #35332.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

Form CP-2/3

MAY 27 2009

Handwritten initials

J. A. TERTELING & SON # 2 KRAMP

7-19-11W / 53
SW NE NE

Contr. ISERN DRILLING CO. County

E. 1814KB Comm. Comp. 2-20-53 IP 430 BOPD

C-80002501110
E.O. 12812

Tops	Depth	Datum
ANH	585	1229
HEEB	2956	-1142
LANS	3096	-1282
ARB	3362	-1548
T.D.	3404	-1590

Casing
 5" 3364 DP 3385: ACID 500:
 DD 3404: ACID 500:
 2 BOPH/12 HRS: PB 3145
 PERF 3100-29: ACID 1000
 9 BOPH/10 HRS

HAMMEKE POOL

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS