



Operator Name: Mike Elwell Lease Name: Snell Well #: 26  
 Sec. 9 Twp. 34 S. R. 11  East  West County: Chautaugua

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run:	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:70%;">Name</td> <td style="width:15%;">Top</td> <td style="width:15%;">Datum</td> </tr> <tr> <td>Lenapha Lime</td> <td>1164</td> <td></td> </tr> <tr> <td>Peru</td> <td>1204</td> <td></td> </tr> </table>	Name	Top	Datum	Lenapha Lime	1164		Peru	1204	
Name	Top	Datum								
Lenapha Lime	1164									
Peru	1204									

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8		40	Portland	8	None consolidated
Production	6 1/4	2 7/8	6	1220	Portland		

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	2" DML-RTG 20 shots 1204-1214	Not tracked or completed as of this date, 08/07/06	

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr.	Producing Method
	<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas	METHOD OF COMPLETION	Production Interval
<input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	<input type="checkbox"/> Open Hole <input type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	<input type="checkbox"/> _____ <input type="checkbox"/> _____

RECEIVED

OCT - 2 2006

KCC WICHITA

CONSOLIDATED OIL WELL SERVICES, INC.  
P.O. BOX 884, CHANUTE, KS 66720  
620-431-9210 OR 800-467-8676

TICKET NUMBER 07167  
LOCATION Bartlesville  
FOREMAN Tracy L. Williams

TREATMENT REPORT & FIELD TICKET  
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-6-06	2379	Snell #26				CO
CUSTOMER <u>Devonian</u>						
MAILING ADDRESS						
CITY						
STATE						
ZIP CODE						
TRUCK #	DRIVER	TRUCK #	DRIVER			
467	Kirk					
208	Dallas					
488	Dusty					
117	Chad C.					

JOB TYPE LS HOLE SIZE 6 3/8 HOLE DEPTH 1863 CASING SIZE & WEIGHT 2 7/8  
CASING DEPTH 1253 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 0  
DISPLACEMENT 2.28 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 5

REMARKS: Ran 4 sks of gel & broke circulation. Ran 240 sks 50/50 pozmix with 5# Kalseal, 5% salt, 2% gel & 40# Phenaseal. Shut down & washed up behind plug. Pumped plug to bottom & set float shoe. Shut in

Circulated cement to surface

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE Production Casing		800.00
5406	46	MILEAGE		144.90
5402	12.53	Footage		213.01
5407	11.34 Ton	Ton Mileage		542.22
5502C	4 hrs & 2 trucks	80 Vac's		720.00
1105	50#	Cottonseed Hulls		12.00
1107A	120#	Phenaseal		180.00
1110A	1200#	Kalseal		432.00
1111	600#	Granulated Salt		174.00
1118B	200#	Premium Gel		98.00
1123	6500 gal	City Water		83.20
1124	240 sks	50/50 Pozmix		2184.00
4408	1	2 1/2" Rubber Plug		18.00
RECEIVED				
KCC WICHITA				
6.3%				
			SALES TAX	16
			ESTIMATED TOTAL	<del>5684.99</del>

AUTHORIZATION # 206021

TITLE \_\_\_\_\_

DATE 6/6/06  
\$ 5684.99



**CONSOLIDATED**  
**OIL WELL**  
**SERVICES, INC.**  
 AN INFINITY COMPANY

**REMIT TO**  
 Consolidated Oil Well Services, Inc.  
 Dept. 1228  
 Denver, CO 80256

**MAIN OFFICE**  
 P.O. Box 884  
 Chanute, KS 66720  
 620/431-9210 • 1-800/467-8676  
 FAX 620/431-0012

INVOICE

Invoice # 206021

Invoice Date: 06/14/2006 Terms:

Page 1

DEVONIAN  
 C/O MIKE ELWELL  
 1648 CRESENT ROAD  
 LAWRENCE KS 66044  
 ( ) -

*pd*

SNELL #26  
 07167  
 6/6/06

Part Number	Description	Qty	Unit Price	Total
1105	COTTONSEED HULLS	50.00	.3400	17.00
1107A	PHENOSEAL (M) 40# BAG)	120.00	1.0000	120.00
1110A	KOL SEAL (50# BAG)	1200.00	.3600	432.00
1111	GRANULATED SALT (50 #)	600.00	.2900	174.00
1118B	PREMIUM GEL / BENTONITE	700.00	.1400	98.00
1123	CITY WATER	6500.00	.0128	83.20
1124	50/50 POZ CEMENT MIX	240.00	8.8500	2124.00
4402	2 1/2" RUBBER PLUG	1.00	18.0000	18.00

  

Description	Hours	Unit Price	Total
117 80 BBL VACUUM TRUCK (CEMENT)	4.00	90.00	360.00
202 TON MILEAGE DELIVERY	1.00	547.72	547.72
428 80 BBL VACUUM TRUCK (CEMENT)	4.00	90.00	360.00
467 CEMENT PUMP	1.00	800.00	800.00
467 EQUIPMENT MILEAGE (ONE WAY)	46.00	3.15	144.90
467 CASING FOOTAGE	1253.00	.17	213.01

RECEIVED  
 OCT - 2 2006  
 KCC WICHITA

Parts:	3066.20	Freight:	.00	Tax:	193.16	AR	5684.99
Labor:	.00	Misc:	.00	Total:	5684.99		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

BARTLESVILLE, Ok  
 P.O. Box 1453 74005  
 918/338-0808

EUREKA, Ks  
 820 E. 7th 67045  
 620/583-7664

OTTAWA, Ks  
 2631 So. Eisenhower Ave. 66067  
 785/242-4044

GILLETTE, WY  
 300 Enterprise Avenue 82716  
 307/686-4914

THAYER, Ks  
 8655 Dorn Road 66776  
 620/839-5269