

4-27-87

6-140-72

API NUMBER 15-163-00999-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NE, SEC. 17, T 10 S, R 18 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Lease Name Ordway Well # #1 A

Operator: Davis Bro. Oil Prod. Inc.
Name & Address One Williams Center
S. 2000
Tulsa, Ok. 74172

County Rooks
Well Total Depth 3731 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 220' CWC

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cmt. License Number _____

Address Hays, Kansas 67601

Company to plug at: Hour: _____ Day: 27 Month: April Year: 19 87

Plugging proposal received from Chuck Arnold

(company name) Davis Bro. (phone) _____

were: 5 1/2" csg @ 3729' w/cmt NA; DV @ 1574' w/500 sx.
Perf. @ 3458 - 3728.

Ordered 200 sx 65/35 Poz, 10% Gel, 2% Lite w/1/4# Flo-cele and 5 sx Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00 A.M Day: 27 Month: April Year: 19 87

ACTUAL PLUGGING REPORT Checked 8 5/8" S.P. Pressured up - O.K.

Pumped in 5 1/2" csg 190 sx w/1/4# Flo -cele and 5 sx Hulls.

Max Psi. 500#

Shut in Psi. 400#.

RECEIVED
STATE CORPORATION COMMISSION
5-11-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 5-15-87

Signed Dennis L. Hamel (TECHNICIAN)
Dennis Hamel

INV. NO. 16900