

1-6

4R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,992-0000

S2 SE NE /4 SEC. 17, 10 S, 18 W
2970 feet from S section line
660 feet from E section line

Operator license# - Lease Ordway 'A' well # 4

Operator: Kansas Corporation Commission County Rooks

Address: State Fee Fund Plugging Well total depth 3680 feet
2301 E. 13th Street Conductor Pipe: 0 inch @ 0 feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 138 feet
w/120 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 6 Month: January Year: 94

Plugging proposal received from: Dennis L. Hamel

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: 4 1/2" casing set @ 3680' w/560 sxs. cement. Perf. @ 3361' - 3440'. Perf. @ 1460' - Dakota 820' - W.L.M. 1808'.

Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls plus 8 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 6, Month: January, Year: 94

Actual plugging report: R.I.H. w/tubing to 3100'. Spot 8 sxs. gel followed with 50 sxs. cement balance at bottom. Pulled tubing to 2100'. Circulated cement to surface from 2100' w/175 sxs. cement. Pulled tubing. Squeezed casing with 25 sxs. additional cement. Max. 1000#. Hooked-up to 8 5/8" S.P. Squeezed 10 sxs. cement to Max. 1000#.

Remarks: Vincent Hrabe Dec. - Operator of record.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2165 GL

I did[X] / did not[] observe the plugging.

Dennis L. Hamel

HD

(agent)

RECEIVED
STATE CORPORATION COMMISSION
Form CP-2/3 1-13-94
JAN 15 1994