

To: 6 041096
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-12
API NUMBER 15- 163-21,991-0000
NW SW NW, SEC. 21, T 10 S, R 18 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # NA

Operator: Vincent J. Hrabec
Name & Address: % Northwestern Supply Co.

3630 feet from S section line
4950 feet from E section line
Lease Name Ordway F Well # 3
County Rooks 118.30

Well Total Depth 3640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 5/8 feet 135' w/125 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00 A.M. Day: 12 Month: Oct Year: 19 89

Plugging proposal received from Terry Richardson

(company name) N. W. Supply Co. (phone) _____

were: 4 1/2" casing set at 3638' w/550 sks. Perf at 3278' - 3506';

Well sq but intervals N.A.

Ordered 200 sks 65/35 poz 8% gel w/1/2# f.c. 20 sks gel plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 7:30PM Day: 12 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Oct. 12, 1989 Run tubing and paker to 1400'. Set packer.

Pumped 25 sks cement and 20 sks gel down tubing plugged bottom at 1500 psi.

Perforated at 1360' and 870'. Pumped 100 sks cement down 4 1/2" at 1200 psi. Max 500 psi.

Shut in. Pumped down annulus. 0 cement 500 psi.

Oct. 16, 1989 Checked cement top 15'.

RECEIVED
STATE CORPORATION COMMISSION
1-3-90
JAN 3 1990

Remarks: (If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)
Dennis Hamel

INVOICED
DATE 1-12-90
INV. NO. 27020
10-12

FEB 09 1990

Marvin Miller