

4-14 15-163-01867-0000  
API NUMBER 15- 7-18-62

6 041026

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SW NW, SEC. 21, T 10 S, R 18 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # NA

Lease Name Ordway F Well # 2

Operator: Vincent J. Hrabe  
Name & Address: % Northwestern Supply Co.  
Box 1753  
Hays, Ks. 67601

County Rooks 115.70  
Well Total Depth 3560 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 161' w/115 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement License Number \_\_\_\_\_  
Address Russell, Ks.

Company to plug at: Hour: 8:00 AM Day: 14 Month: April Year: 19 89

Plugging proposal received from Earl Thomason

(company name) NW Supply Co. (phone) \_\_\_\_\_

were: 4 1/2" casing set at 3559' w/NA sks. Top perf at 3352' - 60'. Shot casing at 2200'; 1900'; 1700'; 1500'; 870'; no casing recovered.

Ordered 300 sks 65/35 Poz 8% Gel w/1/4" F.C. plus 8 sks Hulls.

5-10-89  
MAY 10 1989

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 14 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1610'; spotted 150 sks cement;

cement circ to surface; pulled tubing; hooked up to 4 1/2" casing; pumped add. 75 sks cement in csg. Max 1000#. Shut in 800#.

Pumped in 8 5/8" casing 75 sks cement w/1/4" F.C. plus 2 sks Hulls mixed in cement.

Max 600# S.I. 400#. psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)  
Dennis L. Hamel

DATE 5-11-89

INV. NO. 24776

JUN 12 1989 AUG 08 1989 FEB 12 1990