

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00912-00-00
Spot: CSENESW Sec/Twnshp/Rge: 22-10S-18W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: EILERS B Well Number: 1
County: ROOKS Total Vertical Depth: 3675 feet

Operator License No.: 32688
Op Name: H & R WELL SERVICES INC.
Address: 17509 COUNTY ROAD 14
FT. MORGAN, CO 80701

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 177 150 SX CMT
Production: Size 4.5 feet: 3668 150 SX CMT
Liner: Size feet: 8119.44

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/22/2001 9:00 AM
Plug Co. License No.: 32688 Plug Co. Name: H & R WELL SERVICES INC.
Proposal Rcvd. from: FRANK HUTTO Company: H & R WELL SERVICES INC. Phone: (970) 867-9007

Proposed Salt Section Top 1690'.
Plugging Casing log shows bad pipe.
Method: Bad in Dakota

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/23/2001 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

November 22, 2000 - Ran tubing to top of fish 1725'.
Swift Services pumped 350 sxs 60/40 pozmix - 10% gel with 900# hulls. Shut in on vacuum.
January 12, 2001 - Pumped total of 215 sxs with 500# hulls.
At shut in cement 300' from surface.
January 25, 2001 - Allied ran wireline - found T.D. of 454'.
July 6, 2001 - Swift Services pumped 40 sxs Swift Multi Density cement.
Max. P.S.I. 800#.
Backside has hole in surface pipe.
Will need to dig out and verify cement.
July 23, 2001 - Dug out 8 5/8" x 4 1/2". Found no cement in surface pipe. Filled with 2 yards Redi-Mix.

KANSAS CORPORATION COMMISSION
7-25-01
JUL 25 2001
CONSERVATION DIVISION

Remarks: 112200TUBING100%RW. 01122001CASING100%RW. 07062001CASING100%DH.07232001TOPPED OFF100%RW

Plugged through:

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICE
DATE 7-25-01
WV. NO. 2002060132

Form CP-2/3

JUL 24 2001

