

7-20 15-163-01878-0001

6 040931

6-11-63

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

C SE SE, SEC. 23, T 10 S, R 18

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Operator: Davis Bro. Oil Prod Inc.
Name & Address: One Williams Center
S. 2000
Tulsa, Ok. 74172

feet from S section line
feet from E section line

Lease Name Shepard B Well # 2

County Rooks 118.79

Well Total Depth 3655 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 168' w/130

Abandoned Oil Well Gas Well Input Well SWD Well D&A
RTKCC

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Chuck Arnold

(company name) Davis Brothers (phone)

were: 4 1/2" casing set at 3654'. Top perf at 3528' to 3623'. Perf anhy

1500' and top Dakota 900'. (three holes)

Tubing fish at 2855'.

Ordered 300 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 7 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15PM Day: 20 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 180 sks cement w/1/4# Flocele plus

3 sks Hulls. Max 350# S.I. 350# Psi.

Pumped in 8 5/8" casing 60 sks cement w/1/4# Flocele plus 3 sks Hulls mixed

in cement. Max 300# S.I. 300 Psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-20-88

INV. NO. 22292

Signed Dennis L. Hamel (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 9-16-88 SEP 16 1988 CONSERVATION DIVISION Wichita, Kansas