

6 041306

6-24 15-163-19414-0000'19

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 4-6-1962

SW SE NW, SEC. 24, T 10 S, R 18 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Operator: Davis Bros. Oil Prod. Inc.

Name & Address: One Williams St.

S. 2000

Tulsa, Oklahoma 74172

2970 feet from S section line

3630 feet from E section line

Lease Name Shepard Well # C-4

County Rooks 116.61

Well Total Depth 3588 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 179' w/125sx.

Abandoned Oil Well Gas Well Input Well SWD Well: D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 24 Month: June Year: 19 91

Plugging proposal received from Chuck Arnold

(company name) Davis Bros. (phone)

were: 4 1/2" casing set at 3587' w/275 sks. cement: perms. at 3304' to 3559';

Perf. anhy. at 1425'; perf. base dakota at 800'

Ordered 250 sks. 60/40 poz. 10% gel. w/1/4 lb. flocele plus 5 sks. hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: P.M. Day: 24 Month: June Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing w/25 sks. cement w/1/4 lb. flocele plus

pumped in add. 225 sks. cement w/1/4 lb. flocele and 400# hulls mixed in cement.

Cement circulated from 800' to surface from 8 5/8" S. P.: Shut in same.

Max. 600 lb. S.I. 100 lb.

RECEIVED STATE CORPORATION COMMISSION 7-11-91

JUL 11 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-22-91

INV. NO. 32358

File S.

Signed Dennis L. Hamel (TECHNICIAN)