

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23326-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 27-10S-18W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: EILERS Well Number: 1
County: ROOKS Total Vertical Depth: 3680 feet

Operator License No.: 30407
Op Name: BLACK PETROLEUM COMPANY
Address: PO BOX 12922
WICHITA, KS 67277

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 246
Production: Size feet:
Liner: Size feet:

\$119.60

Well Type: DH UIC Docket No: Date/Time to Plug: 06/30/2001 9:00 AM

Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC

Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud throught dirll pipe.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 06/30/2001 11:15 AM

KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3640' w/25 sxs. Ar buckle at 3654'.
2nd. Plug at 1460' w/25 sxs. Anhydrite 1427' - 1461'.
3rd. Plug at 850' w/100 sxs. Dakota 538' - 838'.
4th. Plug at 300' w/40 sxs. Surface pipe at 246'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 7-5-01
INV. NO. 2002060013
RECEIVED
KANSAS CORPORATION COMMISSION
7-5-01
JUL 5 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)