

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,447-0000
SW SW NW Sec. 26, T 10 S, R 18 W
2970 feet from N/S section line
4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name Shepard Well # B-1

Operator: Liberty Operations & Completion
Name & 308 West Mill Street
Address Plainville, Ks. 67663

County Rooks

Well Total Depth 3750 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 217

121.88

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Pioneer Drilling License Number 5665

Address 308 West Mill, Plainville, Ks.

Company to plug at: Hour: PM Day: 30 Month: August Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Don Armbuster

(company name) Pioneer Drilling Company (phone)

were: Order 200 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 9:15 PM Day: 30 Month: August Year: 1984

ACTUAL PLUGGING REPORT

- 1st plug @ 3680 w/20 sks
- 2nd plug @ 1420 w/20 sks
- 3rd plug @ 780 w/100 sks 1 sk flo-cel
- 4th plug @ 250 w/40 sks
- 5th plug @ 40 w/8 5/8" plug 1/2 sk hulls and 10 sks cmt

Remarks: 10 sks in Rat Hole
Cemented by Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
9-4-84 Signed
SEP 04 1984

Gilbert P. Leiker
(TECHNICIAN)

INVOICED
DATE 9-12-84
AMOUNT 3622

FORM CP-2/3 SH
Rev. 9-82
aug 31
33