

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20730-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 27-10S-18W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: EILERS EAST Well Number: 1
County: ROOKS Total Vertical Depth: 3651 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3646 w/125 sxs cmt
Surface Casing Size: 8.625 feet: 199 w/125 sxs cmt

9/118.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2003 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY LENDENMUTH Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging Fluid level 50' from surface. Top off fish 1063'. Unable to fish.
Method: Spotted 250 gal - 28% acid on bottom. PTOH. Shut in.
10-02-2003 - Fluid 250' from surface.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/02/2003 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1050'. Swift Services pumped 70 sxs 60/40 pozmix - 10% gel cwc.
PTOH. Squeezed with 155 sxs cement with 300# hulls.
Max. P.S.I. 600#. S.I.P. 200#.
Hooked up to 8 5/8" - pumped 25 sxs cement with 200# hulls.
Max. P.S.I. 400#. Blew hole in 8 5/8" deep cwc. up backside.

RECEIVED
10-8-03
OCT 08 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

10-7-03
2004060589

Form CP-2/3

OCT 06 2003

BGH OIL PROPERTIES,
E.A. BEPPY

#1 EILERS EAST

27-10-18W
SE NW NE

BOX 325, NEWTON, KS.
CONTR DREILING OIL CO.

CTY ROOKS

GEOL LAWRENCE GRAY

FIELD EILERS

N 2051 GL CM 9/5/77 CARD ISSUED 11/17/77 P 23 BOPD, NW

ARB OH 3646-51

+	+
+	+

API 15-163-20,730

LOG	TOPS	DEPTH	DATUM
ANH		1416	- 635
TOP		3037	- 986
HEES		3255	-1204
TOR		3271	-1220
LANS		3296	-1245
BKC		3520	-1469
CONG		3544	-1493
ARB		3649	-1598
LTD		3650	-1599
RTD		3651	-1600

8-5/8" 199/125sx, 4 1/2" 3646/125sx
DST (1) 3440-95/30-45-30-45, REC 100'
HOOM W/SHOW FREE O, SIP 361-323#
FP 78-90#
MICT - CO, (KC OH) NAT, POP, P 22 BOPD
(GR 37°)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS